

नाशिक महानगरपालिका नाशिक
विद्युत विभाग

ई- कोटेशन नोटीस क्र. १४ सन २०१५-१६

कामाचे नाव :- नाशिक पश्चिम कालिदास कलामंदिर येथील नविन बुकिंग ऑफिस इमारतीस
वायरिंग करणे.

प्राकलण र.रु. - ४८,१२५/-

कोटेशन फॉर्म मिळण्याचे ठिकाण - कार्यकारी अभियंता कार्यालय, विद्युत विभाग,
राजीव गांधी भवन.

कामाची मुदत : १ महिना

काम करणेचे ठिकाण : नाशिक महानगरपालिका, नाशिक

कोटेशन फॉर्म मिळण्याची तारीख : दि.२२/ ०१ /२०१६ ते दि. २८ /०१/२०१६

कोटेशन जमा करण्याची अंतिम तारीख : २९/ ०१/२०१६ रोजी दुपारी ३.०० वाजेपर्यंत

कोटेशन जमा करण्याचे ठिकाण : विद्युत विभाग,
राजीव गांधी भवन, नाशिक म.न.पा.,
शरणपुर रोड, नाशिक

Sd/-

उप अभियंता (वि.)

नाशिक महानगरपालिका, नाशिक.

NASHIK MUNICIPAL CORPORATION
ELECTRICAL DEPARTMENT

'E' Quotation form No. 14

(2015-16)

Name of work :- E.I. Work at Kalidas Kalamander Bookings office and fans erection in
Nashik West Div.

Cost put 'Quotation Rs. 48,125/-

Time limit :- 7 Days

SCHEDULE 'B' OF B- 1 'E' QUOTATION FORM

Sr.No.	Item	Qty	Rate	Per	Amount
1	(1-9-16) Point Wiring Point wiring in PVC trunking (casing-capping) with 1.0 sqm FR grade copper wire with flush type switch and required accessories as per specification No: WG-PW/SW	12	304	Point	3648.00
2	(1-9-13) Plug Point Wiring for plug on board with Switch socket with copper wiring and earthing as per specification No:WG-PW/SW	5	88	Point	440.00
3	(1-9-19) Independent Plug Point Point wiring for independent plug in PVC trunking (casing-capping) with 1.0 sq.mm FRLS grade copper wire with flush type switch and required accessories as per specification No: WG-PW/SW	2	350	Each	700.00
4	(1-7-13) Power Point Supplying and erecting flush type shockproof plug socket 6A.& 16A (6 pin) with 16A switch combined with indicator lamp and fuse with gang box on wooden board.	1	195	Each	195.00
5	(1-6-2) Mains 2x1.5 Supplying & erecting mains with 2x1.5 sq.mm.and earth wire 1.5 sqmm FRLS PVC copper wire, in rigid PVC conduit min.20mm dia, as per specification No:	20	108	Mtr	2160.00
6	(1-6-4) Mains 2x2.5 Supplying & erecting mains with 2x2.5 sq.mm.and earth wire 1.5 sqmm FRLS PVC copper wire, in rigid PVC conduit min.20mm dia, as per specification No:	5	129	Mtr	645.00
7	(5-3-3) SPMCB Supplying, erecting & marking SPMCB 6A to 32A, B- series (for lighting) in provided distribution board as per specification No. WR/MCB	1	162	Each	162.00
8	(5-1-1) D.P. Switch Supplying and erecting Insulated D.P. switch surface type/ flush type 32A 250V with indicator lamp & fuse as per specification No. SW-SWR/BDP	3	170	Each	510.00
9	(2-1-10) Tube Rod Supplying and erecting T8 Fluroscnt tube day light 1200mm 36 W.	7	57	Nos	399.00

10	(2-4-4) Tube set Supplying & erecting approved make 1 x 36/40W white stove enamelled / powder coated box type fluo.fitting with 40 W electronic ballast having pf > 0.9 fixed at ceiling or on wall as per specification No. FG-IDF/BFF	7	581	Nos	4067.00
11	(2-13-3) Ceiling fan Supplying and erecting regular/ standard model Ceiling fan of 1200 mm. sweep complete erected in position as per specification no. FG	2	1794	Each	3588.00
12	(2-12-10) Fan Regulators Supplying and erecting electronic type step regulator for ceiling fan 600/ 900/ 1200/ 1400 mm. sweep, complete erected on provided	2	201	Each	402.00
13	(2-13-17) Exhaust Fan Supplying and erecting Exhaust fan heavy duty 230 V, A.C. 50 cycles 375/380 mm. 900 RPM complete erected in position as per specification no. FG-FN/EXF	2	3405	Each	6810.00
14	(7-1-15) Cable Supplying, erecting & terminating PVC armoured cable 4 core 10 sq mm aluminium conductor with continuous 5.48 sq mm (12 SWG) G.I. earth wire complete erected with glands & lugs, on wall/ trusses/pole or laid in provided trench/ pipe as per specification no. CB-LT/AL	45	171	Mtr	7695.00
15	(16-1-2) Trench in Tar Road Making the trench in Hard murum/Tar road of suitable width and depth as per IS for laying provided L.T cable up to 10 sq.mm.complete. As per specification No. CW-EXN-CTR	30	153	Mtr	4590.00
16	(16-5-5) G. I. Pipe Supplying and erecting ISI mark G.I.pipe 40 mm. dia. 'B' class at position with accessories. As per specification No. CW-PLB/GP	12	344	Mtr	4128.00
17	(9-1-1) Earthing Supplying and erecting Galvanised cast iron earth plate size 60 x 60 x 0.6 cm complete with all materials, testing & recording the results as per specification No. EA-EP	1	4018	Nos	4018.00
18	(2-13-5) Wall Fan Providing and erecting bracket fan 400 mm. sweep A. C. 230 volts 50 cycles 1350 R.P.M. Oscillating type, plastic or metal blades chrome plated guard with regulator and moisture proof treatment to winding and with 'E' class insulation and marking Sr. No. and date of erection.	2	1984	Each	3968.00
				TOTAL	48125.00

I/We are hereby agreed to exeute the above work at % above / below (In words ppercent) the estimated rates.

Signature & stamp of Contractor

Sd/-
Deputy Engineer (Ele.)
Nashik Municipal Corporation,