

नाशिक महानगर पालिका, नाशिक.
उद्याने व वृक्ष प्राधिकरण विभाग,
कोटेशन नोटीस

जा.क्र./उद्यान/स.क.अ.१/४४/२०१७, दि. २५/०९/२०१७

कामाचे नाव :- नविन नाशिक विभागातील नविन प्रभाग क्र. ३१ मधिल सप्तश्रृंगी देवी मंदिर, स्वामी समर्थ नगर
येथिल खुल्या जागेची संरक्षक भिंत दुरुस्त करणे बाबत...

कामाची मुदत :- ३० दिवस

कोटेशन फॉर्म मिळण्याची तारीख :- दि. २६/०९/२०१७ ते दि. ०३/१०/२०१७

कोटेशन फॉर्म स्विकारण्याची अंतिम तारीख :- दि. ०३/१०/२०१७ दु. ३.०० वाजेपर्यंत

कामाचा तपशिल :

I. No.	Description of Item	Quantity	Rate		Per	Amount	
			Rs.	Ps.		Rs.	Ps.
1	Dismantling stone masonry in lime or cement including stacking the materials as directed with all leads, lifts, complete. Additional item Spec. No. As directed by Engineer in charge. DSR-15-16, Sr. No:- 648, P. No:- 217	4.22 Sqmt.	204	80	Cumt.	864	25
2	Providing uncoursed rubble masonry of trap/granite/quartzite/gneiss stones in cement mortar 1:6 in foundation and plinth of inner walls / in plinth of external walls including bailing-out water manually, striking joints on unexposed faces and watering complete. Spec. No. Bd.H.1 Page No. 329 DSR-15-16, Sr. No:- 105, P. No:- 71	1.65 Cumt.	4093	20	Cumt.	6,753	78
3	Providing and casting in situ cement concrete M-15/1:2:4 of trap/granite/quartzite/gneiss metal, moulded or chamfered as per drawing or as directed for coping to plinth or parapet , including centering form work, compacting, covering newly laid concrete by gunny bag, plastic or tarpaulin. roughening them if special finish is to be provided and curing and finishing if required etc. complete. (The cement mortar 1:3 plasters is considered for rendering uneven and honey-combed surface only. wooden planks/shuttering will not be allowed. The shuttering should be of waterproof plywood or tailer made angle and steel plate.) Spec.No.Bd.E.3 Page No.288/IS 456:2000 DSR-15-16, Sr. No:- 38, Page No:- 20	0.29 Cumt.	5755	30	Cumt.	1,669	03
4	Providing and casting in situ cement concrete M-20 of trap/granite/quartzite/gneiss metal, moulded or chamfered as per drawing or as directed for bed blocks, foundation blocks , including centering form work, compacting, covering newly laid concrete by gunny bag, plastic or tarpaulin. roughening them if special finish is to be provided and curing and finishing if required etc. complete. (The cement mortar 1:3 plasters is considered for rendering uneven and honey-combed surface only. wooden planks/shuttering will not be allowed. The shuttering should be of waterproof plywood or tailer made angle and steel plate.) DSR-15-16, Sr. No:- 39, P. No :- 27	0.81 Cumt.	6341	00	Cumt.	5,136	21
5	Providing sand faced plaster externally in cement mortar using kharsalia / kasaba or similar type of sand in all position including base coat of 15mm thick in C.M. 1:4 using waterproofing compound at 1kg.per cement bag. curing the same for not less than 3 days and keeping the surface of the base coats rough to receive the sand faced treatment 6 to 8mm thick in C.M. 1:4, finishing the surface by taking out grains and curing for fourteen days, scaffolding etc. complete. Spec.No.Bd.L.7 Page No. 369 DSR-2015-16, Sr. No:- 149, Page No:- 94	14.09 Sqmt.	405	00	Sqmt.	5,706	45

6	Providing patta on plastered surface 12 mm to 15 mm thick in c.m. 1 : 3 In line and level including neat finishing, scaffolding, curing etc. complete. b)100mm wide DSR-15-16, Sr. No:- 160, Page No:- 95	13.50 Rmtr.	35	50	Rmtr.	479	25
7	Providing tuck pointing with cement mortar 1:3 for stone masonry including scaffolding and curing complete. Spec. No. Bd. L. 16 Page No.373 DSR-15-16, Sr. No:- 155, Page No:- 95	8.55 Sqmt.	102	80	Sqmt.	878	94
8	Providing and fabricating structural steel work in rolled sections like joists, channels angles, tees etc. as per detailed designs and drawing including fixing in position without connecting plates, braces etc. and one coat of anticorrosive paint and over it two coat of oil paintings of approved quality and shade complete. Spec.No.Bd.C.2 page No. 275 DSR-15-16, Sr. No:- 26, Page No:- 15	0.11 M.T.	61908	00	M.T.	6,809	88
9	Providing and erecting chain link fencing 1:6 M. height with G.I. chain link of size 50 × 50mm 8 gauge thick and fixed 75 mm above Ground level vertical M.S Angle of 40 × 40 × 6mm size embedded in C.C. block of 1:4:8: mix of size 450 × 450 × 670 mm at 1.75Mc./c. with iron bar 16 mm dia. as hold fast including welding link with angle frame at 30 cm c/c nuts and bolts and horizontal MS. Angle at top and bottom of 25 × 25× 5 mm size and vertical M.S. flat 35 × 5mm and 25 × 5 mm horizontal including cross support of 40 × 40 × 6 mm Angle both sides at every corner or bends embedded in concrete blocks of 1:4:8 of size 450 × 450 × 670 mm including 3 coats oil painting etc. complete. Additional item Spec. No. As directed by Engineer in charge DSR-2015-16, Sr. No:- 675, Page No:- 221	14.00 Rmtr.	1451	10	Rmtr.	20,315	40
10	Repairing chain link fencing 1:6 M. height excluding G.I. chain link, M.S Angle, C.C. block, M.S. flat etc. complete. Additional item Spec. No. As directed by Engineer in charge	10.00 Rmtr.	75	60	Rmtr.	756	00
					TOTAL	49,369	19

एकूण प्राकलन रक्कम रूपये :- ४९,३६९/-

अक्षरी रक्कम रूपये :- एकोणपन्नास हजार, तिनशे एकोणसत्तर मात्र

अटी शर्ती :

१) सदरकामी लागणारे कोणत्याही प्रकारचे आवश्यक साहित्य मनपा पुरविणार नाही तसेच सदरकामी होणारा मजुरीचा, वाहतुकीचा व ईतर अनुशंगिक खर्च हा मक्तेदारास करावयाचा आहे. २) सदर कामाबाबतची सविस्तर माहिती व कामाचे कोटेशन फॉर्म विभागाचे सहा. कनिष्ठ अभियंता यांचेकडे सार्वजनिक सुटिचे दिवस सोडुन उपरोक्त नमुद मुदतीत कार्यालयीन वेळेत नविन नाशिक विभागाचे कार्यालयात उपलब्ध करून देण्यात येईल. ३) सदर काम विभागाचे सहा. कनिष्ठ अभियंता सुचवितील त्याप्रमाणे विहित मुदतीत पुर्ण करून घ्यावे लागेल. ४) सदर कामाचे कोटेशन दर स्विकारण्याचा अथवा नाकारण्याचा अंतिम अधिकार हा मा. उद्यान अधिक्षक सा. यांचा राहिल ५) सदरकामी कोणत्याही प्रकारचे आगाउ देयक मनपाकडुन मिळणार नाही.

ज्या कोणास वरील नमुद काम वरील नमुद मुदतीत व अटीशर्तीनुसार करावयाचे असेल त्यांनी याबाबतचे आपले कोटेशन दर विहित नमुन्यात बंद पाकिटात उद्यान व वृक्ष प्राधिकरण विभागाचे नविन नाशिक विभागाचे कार्यालयात दि. ०३/१०/२०१७ रोजी दु. ०३.०० वाजेपर्यंत आणुन घ्यावेत.

प्र. उद्यान अधिक्षक
नाशिक महानगर पालिका, नाशिक.