नाशिक महानगरपालिका, नाशिक

विद्युत विभाग

ई - कोटेशन नोटीस क्र. सन २०१५ - १६

कामाचे नाव :- नाशिक पश्चिम विभागातील म. न. पा. सफाई कामगार वसाहत रेडक्रॉस आंबेडकर कॉलनी येथील प्यानल बोर्ड ची इनकमिंग केबल बाबत.

प्राकलन रक्कम रुपये :- ४९,७२५/-

ई - कोटेशन मिळण्याचे ठिकाण - wwwnashikcorporation.com वर उपलब्ध आहे.

कामाची मुदत : १ महिना

काम करण्याचे ठिकाण : नासिक महानगरपालिका, नाशिक.

कोटेशन मिळण्याची तारीख : दि. २६ / १० / २०१६ ते दि. ०२ / ११ / २०१६

कोटेशन जमा करण्याची अंतिम तारीख : दि. ०२ / ११ / २०१६ रोजी दुपारी ३.०० वाजेपर्यंत

कोटेशन जमा करण्याचे ठिकाण : विदयुत विभाग,
राजीव गांधी भवन, नाशिक म. न. पा.,
शरणपूर रोड, नाशिक.

Sd/-
उप अभियंता (वि.)
नाशिक महानगरपालिका, नाशिक.

NASIK MUNICIPAL CORPORATION

ELECTRICAL DEPARTMENT

'E' Quotation form No / (2015-16)

Name of the Work :- REPLACEMENT OF DAMAGE L. T. CABLE AT SAFAI KAMGAR VASAHAT REDCROSS IN NASIK DIV.

Cost put ' E' Quotation Rs. Time limit :- 30 days

SCHEDULE ' B' OF B-1 'E' QUOTATION FORM

Sr no	Item	Qty	Rate	Per	Amount
01	**(5-2-13) distribution board** Supplying and erecting metal clad **distribution board**approved make **415/500V, 8 way, 32A**. per way & neutral barconnector complete erected on iron frame/ wooden plank orBoard as per specification No. **SW-SWR/MDB**	01	5565/-	Each	5565/-
02	(7-1-27) **armoured** cable **3½** Supplying, erecting & terminating **PVCarmoured** cable **3½core 120 sq mm aluminium** conductor with continuous**12.97 sq mm (8 SWG)** G.I. earth wire complete erected withglands & lugs, on wall/ trusses/pole or laid in providedtrench/ pipe as per specification no. **CB-LT/AL**	60 mtr	736/-	Mtr	44,160/-
			TOTAL AMOUNT		**49,725/-**

I/We are hereby agreed to execute the above work at % (In words…… …… percent) above/ below the estimated rates.

Signature & stamp of contractor

Sd/-

DY. Engineer (Ele.)