

नाशिक महानगरपालिका नाशिक  
विद्युत विभाग

ई- कोटेशन नोटीस क्र. १ सन २०१९-२०

कामाचे नाव :- पंचवटी प्र.क्र.६,(ब) मधील विद्यानगरी येथील अभ्यासिकेस विद्युतीकरण करणे.

प्राकलन र.रु. — ४९,५२०/-

ई-कोटेशन फॉर्म मिळण्याचे ठिकाण — [www.nmc.gov.in](http://www.nmc.gov.in) वर उपलब्ध आहे.

कामाची मुदत : १ महिना

काम करणेचे ठिकाण : नाशिक महानगरपालिका, नाशिक

कोटेशन फॉर्म मिळण्याची तारीख : दि. १४/०८/२०१९ ते दि. २१/०८/२०१९

कोटेशन जमा करण्याची अंतिम तारीख : २२/०८/२०१९ रोजी दुपारी ३.०० वाजेपर्यंत

कोटेशन जमा करण्याचे ठिकाण : विद्युत विभाग,  
राजीव गांधी भवन, नाशिक म.न.पा.,  
शरणपुर रोड, नाशिक

Sd/-

कार्यकारी अभियंता (वि.)  
नाशिक महानगरपालिका, नाशिक.

**NASHIK MUNICIPAL CORPORATION  
ELECTRICAL DEPARTMENT**

‘E’ Quotation form No. 1

(2019-20)

Name of work:- Electrification work study room at vidyanagari makhmalabad p.no.6 (B)  
panchavati division,NMC

Cost put ‘Quotation Rs. 49,520/-

Time limit :- 30 Days

**SCHEDULE ‘B’ OF B- 1 ‘E’ QUOTATION FORM**

Sr.No.	Items	Qty.	per	Rate	Amount
1	1-9-25 Point wiring in PVC trunking (casing-capping) with 1.5 sq.mm (2+1E) FR grade copper wire, modular type switch,earthing and required accessories as per specification No:WG-PW/SW	24	Each	433	10392
2	1-9-13 Wiring for plug on board with Switch socket, copper wiring and earthing as per specification No: WG-PW/SW	4	Each	95	380
3	1-7-13 Supplying and erecting flush type shockproof plug socket 6A & 16A (6 pin) with 16A switch combined with indicator lamp and fuse with gang box on wooden board.	2	Each	167	334
4	1-3-1 Supplying & erecting mains with 2x1.5 sq.mm F.R copper PVC insulated wire laid in provided conduit/trunking/inside pole/Bus bars or any other places as per specification No: WGMA/BW	20	Mtr.	35	700
5	1-3-11 Supplying & erecting mains with 3x2.5 Sq.mm F.R copper PVC insulated wire laid in provided conduit/trunking/inside pole/Bus bars or any other places as per specification No: WGMA/BW	50	Mtr.	74	3700
6	1.3.13 Supplying & erecting mains with 3x4 sq.mm FR copper PVC insulated wire laid in provided conduit/trunking/inside pole/Bus bars or any other places as per specification No: WGMA/BW	25	Mtr.	105	2625
7	1.2.10 Supplying and erecting PVC trunking (PVC casing-n-capping)of size 25 mm with accessories on wall/ceiling as per specification No: WG-MA/CON.	5	Mtr.	35	175
8	2.1.23 Supplying & erecting LED 20W tube light fitting (4 feet) with aluminium housing, heat sink, integrated HF electronic driver complete	6	Each	878	5268
9	2.12.3 Supplying and erecting regular/ standard model ceiling fan of 1400mm. sweep complete erected in position as per specificationno. FG-FN/CF	5	Each	1895	9475
10	1.8.23 Supplying and erecting ISI mark modular type (two module) electronic step regulator for fan, duly erected on provided plate and box with wiring connections complete. Note: Add Rs 57/- for additional two module box with double mounting plate if required.	6	Each	348	2088
11	2.13.2 supplying & fixing Anchor type fastener Fan hook with 2 Nos of 10mm dia 75 mm long with necessary materials for Celling Fan.	6	Mtr.	92	552

12	2.13.6 Supplying and erecting 'B' grade G.I. pipe / M.S. pipe down rod duly painted for fan complete erected with PVC three core flexible cable 1 sq. mm copper PVC wire.	6	Each	204	1224
13	2.12.4 Providing and erecting bracket fan 400 mm. sweep A. C. 230 volts 50 cycles 1350 R.P.M. Oscillating type, plastic or metal blades chrome plated guard with regulator and moisture proof treatment to winding and with 'E' class insulation.	1	Each	1940	1940
14	5.1.1 Supplying and erecting double pole switch surface type/ flush type 240V, 32A with indicator lamp & fuse as per specification no. SWSWR/BDP.	2	Each	162	324
15	5.3.3 Supplying, erecting & marking SPMCB 6A to 32A, B- series (for lighting) in provided distribution board as per specification no. SWSWR/MCB	2	Each	164	328
16	5.4.23 Supplying & erecting CRCA sheet metal one way enclosuressuitable for DP MCB /TP MCB /FP MCB erected on angle iron/GI frame complete	1	Each	339	339
17	2.2.5 Supplying and erecting LED street light fitting suitable for 60W lamp, including lamp, with PF > 0.95 class IP 65 and above housing of pressure die cast aluminium alloy and heat sink extruded aluminium complete as per specification No FGODF/FLS-2.	1	Each	221	221
18	2.10.11 Supplying & erecting 10-12W, 230V integral type LED Lampsuitable for B-22/E-27 base.	1	Each	218	218
19	2.12.15 Supplying and erecting exhaust fan medium duty 230 V A.C. 50 cycles 225 mm. 1400 RPM with condenser complete erected in position with necessary materials. Fan motor with moisture proof treatment and 'E' class insulat	0	Each	1623	0
20	9-1-1 Providing earthing with galvanized iron earth plate size 60 x 60 x 0.6 cm complete with all materials, testing & recording the results as per specification no. EA-EP	1	Each	3931	3931

I /We are hereby agreed to exeute the above work at % above / below ( In words ..... percent ) the estimated rates.

Signature & stamp of Contractor

Executive Engineer (Ele.)  
Nashik Municipal Corporation,