

नाशिक महानगरपालिका नाशिक  
विद्युत विभाग

ई- कोटेशन नोटीस क्र.४ सन २०१६-१७

कामाचे नाव :- नाशिक पुर्व प्र.क्र.३८ मधील विविध ठिकाणचे पोल, फीटींगज दुरुस्त करणे.  
प्राकलण र.रु. — ४९,९५०/-

ई-कोटेशन फॉर्म मिळण्याचे ठिकाण — [www.nashikcorporation.com](http://www.nashikcorporation.com) वर उपलब्ध आहे.

कामाची मुदत : १ महिना

काम करणेचे ठिकाण : नाशिक महानगरपालिका, नाशिक

कोटेशन फॉर्म मिळण्याची तारीख : दि.२५/०५/२०१६ ते दि.०२/०६/२०१६

कोटेशन जमा करण्याची अंतिम तारीख : ०३/०६/२०१६ रोजी दुपारी ३.०० वाजेपर्यंत

कोटेशन जमा करण्याचे ठिकाण : विद्युत विभाग,  
राजीव गांधी भवन, नाशिक म.न.पा.,  
शरणपुर रोड, नाशिक

**Sd/-**

उप अभियंता (वि.)  
नाशिक महानगरपालिका, नाशिक.

**NASHIK MUNICIPAL CORPORATION  
ELECTRICAL DEPARTMENT**

‘E’ Quotation form No. 4

(2015-16)

Name of work:- Repairing of street light poles fittings in P.No.38 Nashik East Div.

Cost put ‘Quotation Rs. 49,950/-

Time limit :- 30 Days

**SCHEDULE ‘B’ OF B- 1 ‘E’ QUOTATION FORM**

Sr.No	Item	Qty.	Rate	Per	Amount
1	8-1-2 Erecting departmentally supplied G.I. tubular swaged pole 114.3 x 88.9 x 76.1 mm. dia with 4.5 x 3.65 x 3.25 mm thickness ( 4 + 1.5 + 1.5 m ) length respectively and total 7 m long with pole cap, base plate in provided foundation (weight 113 kg) as per specification No. OH-PL/STP (labour charges only)	10 Nos	450.00	Each	4,500.00
2	16-3-1 Providing cement concrete foundation including excavation for the poles 60 cms. x 60 cms. x 1.2 Mtr. deep in 1:3:6 cement concrete (20 to 25 mm stone metal) and 45 cm x 45 cm. x 45 cm./45 cm. dia. x 45 cm. height plinth duly plastered and with necessary curing and finishing in an approved manner. (for 7 mtr pole )	10 Nos	1320.00	Each	13,200.00
3	2-6-2 Erecting departmentally supplied street light bracket made from 40 mm. dia B class G.I. pipe,0.6 m. in length along with pole cap of 300 mm length and 80mm dia duly with provided leads as per specification No FG-BKT/ BPC (labour charges only)	10 Nos	89.00	Each	890.00
4	9-1-4 Supplying & erecting pipe type earthing with 40mm. dia.G.I. pipe or 20mm dia. G.I. rod complete with all materials as per specification no. EA-EP	10 Nos	1536.00	Each	15,360.00
5	1-4-1 Supplying & erecting mains with ISI mark 2 x 2.5 sq. mm. 1100 V. Grade aluminium PVC insulated and PVC sheathed wires on G.I. bearer wire No. 8 SWG complete erected with required size of porcelain reel insulators and 16 SWG G.I. binding wire.	320 Mtr	50.00	Mtr	16,000.00
Total RS.					<b>49,950.00</b>

I /We are hereby agreed to execute the above work at \_\_\_\_\_ % above / below ( In words ..... perencent ) the estimated rates.

Signature &amp; stamp of Contractor

Sd/-  
Deputy Engineer (Ele.)  
Nashik Municipal Corporation,