

नाशिक महानगरपालिका, नाशिक
विद्युत व यांत्रिकी विभाग
पाणीपुरवठा (यां) विभाग

ई-कोटेशन नोटीस क्र. ५ / २०२१-२२

कामाचे नाव :- मनपाचे शिवाजीनगर जलशुद्धीकरण केंद्र येथील फेज १ व फेज २ येथील क्लोरीन सीसीटी चॅनेल लिकेज दुरुस्ती व फिल्टर हाऊसमधील लेव्हल इंडिकेटर नविन बसविणे व इतर अनुषांगिक दुरुस्तीकामे करणे.

१. कामाची मुदत :- १ महिने

२. कोटेशन फॉर्म मिळण्याचे ठिकाण:- कार्यकारी अभियंता (यां)

राजीव गांधी भवन, मनपा, नाशिक.

३. काम करणेचे ठिकाण:- विषयांकित

४. कोटेशन जमा करण्याची अंतिम तारीख:- दि. ०९/०७/२०२१ ते दि. १५/०७/२०२१

५. कोटेशन जमा करण्याचे ठिकाण:- कार्यकारी अभियंता (यां)

राजीव गांधी भवन, मनपा, नाशिक.

Sd/-
कार्यकारी अभियंता(यां)
मनपा नाशिक

NASHIK MUNICIPAL CORPORATION
WATER SUPPLY DEPARTMENT (MECH)
QUOTATION FORM

Sub :- Repairing and installing Chlorine CCT channel, Filter house level indicator, Filter house door and related maintenance work at Shivajinagar WTP phase 1 & 2 of NMC.

Ref :- E-quotation No. :- /2021-22

NO	DISCRIPATION	QUANTIT Y	RATE	UNIT	AMOUNT
1	Providing pressure grouting at a pressure of 0.56 kg./sqcm in required row/zigzag fashion as specified at 1.5 M interval as per site conditions to stop leakages through water retaining structures to the entire satisfaction of the Engineer-in-charge including material compound, hardening materials, compressor equipment including scaffolding smooth finishing, etc. complete. MJP DSR 19-20 SECTION H I.NO. 6	75.00	854.30	Bag	64072.50
	For Concrete strcture				
2	Drilling 40 mm dia holes in masonry or concrete structure with providing and fixing 0.5 M long G. I. pipe line for perssure grouting including all Material labour cost and machinery charges, etc. complete. MJP DSR 19-20 SECTION H I.NO. 78	22.50	722.00	RMT	16245.00
3	Providing and fixing M.S. grill door 24 kg/sqm of various size as per detailed drawings without hot dip coating, iron fixtures and fastenings and 3 coats of oil painting etc PWD SSR 20-21 I.NO. 39.31	7.92	2704.80	SQ.M.	21422.02
4	Providing and fixing rolling shutter fabricated from steel laths of minimum thickness 0.9 mm with lock plate of 3.15 mm thickness reinforced with 35 x 35 x 5 mm angle section fitted with sliding bolts and handles for both sides, deep M.S. channel section of depth and thickness not less than 65 mm and 3.15 mm respectively with hold fast arrangements, M.S. Bracket plate 300 x 300 x 3.15 mm minimum size and shape with square bar, suspension shaft of minimum 32 mm diameter, hood cover of M.S. sheet not less than 0.9 mm thickness and of any size at top and safety devices including mechanical gear operation arrangement consisting of worm gear wheels and worms of high grade cast iron or mild steel and one coat of red lead primer etc. complete. (I.S. 62481979) (Without mechanical gear)PWD SSR 20-21 I.NO. 39.24	12.00	4288.20	SQ.M.	51458.40
5	Excavation for foundation in Soft rock and old cement or lime masonry foundations including removing the excavated material upto a distance of 50 metres beyond the building area and stacking as directed, including dewatering, preparing the bed for the foundation and necessary back filling with available earth /murum, ramming, watering including shoring and strutting etc. complete (lift upto 1.5m) By Mechanical Means PWD SSR 20-21 I.NO. 21.14	4.50	401.10	CUM	1804.95

6	Providing and laying Cast in situ/Ready Mixcement concrete in M20 of trap/ granite/quartzite/gneiss metal for steps including steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) PWD SSR 20-21 I.NO. 24.06	2.25	7005.80	CUM	15763.05
7	Providing and laying machine cut machine Polished Kota stone flooring 25mm to 30mm thick and required width in plain/ diamond pattern on bed of 1:6 C. M. including cement float, filling joints with neat cement slurry, curing, polishing and cleaning etc. complete PWD SSR 20-21 I.NO. 33.06	13.50	1223.70	SQ.M.	16519.95
8	Providing and fixing steel frame door of angle 40 x 40 x 5 mm with 16 mm dia. mild steel bars horizontally at 10cm c/c for ventilator portion including iron hold fast for the fixing shutters including welding, painting, finishing etc. complete.PWD SSR 20-21 I.NO. 39.36	7.92	1536.20	SQ.M.	12166.70
9	Providing and fixing water level indicator upto 5 M height including M.S. enamelled gauge plate 300 mm wide 3 mm thick, P.V.C. float, providing and fixing required accessories such as pointer, pulleys, nylon thread including cost of all material, labour, etc. complete. MJP DSR 19-20 SECTION J I.NO. 11	6	10272.15	NO.	61632.9
					261085.47
	Add 12% GST				31330.26
	Total				292416.00

I/We hereby agree to execute the above work at _____ % (in words
 _____ percent)
 below/above the estimated rates.

**Signature of Contractor
 With Stamp**

**Executive Engineer
 Nashik Municipal Corporation**