

**NASIK MUNICIPAL CORPORATION  
MECHANICAL DEPARTMENT**

**Name of work:** Providing and laying instrumentation data cable for flow meter at Nilgiribag WTP.

S. N	Item	Qty	Per	Rate	Amount
1	Providing and laying 0.25sq.mm PVC insulated flexible cable, each pair individually shielded with PVC coating and overall shielded data cable, 500V.	111	Mtr	1050.00	116550.00
2	Providing and laying 0.5sq.mm X 3 core PVC insulated flexible shielded supply cable, 500V.	100	Mtr	550.00	55000.00
3	Making trench of suitable width and depth in hard murum / tar road for laying provided cable (PWD DSR 2020-21, 16-1-2)	30	Mtr	193.00	5790.00
4	Providing and laying UPVC flexible pipe 25mm in dia. (PWD Civil DSR 2021-22, Sr No- 353)	80	Mtr	408.00	32640.00
5	Providing and fixing UPVC accessories, fittings, hardware, solution, etc accessories complete.	1	Set	3250.00	3250.00
6	Removing jel making connection to sensors and flow meter again filling jel and giving satisfactory test and trial etc complete.	1	Job	15000.00	15000.00
				Total	228230
				GST@12%	27388
				Total	255618

I / We hereby agreed to execute the above work at \_\_\_\_\_ % Below \_\_\_\_\_ %Above the estimate rate.

Contractor

Deputy Engineer  
Mechanical Department

नाशिक महानगरपालिका, नाशिक  
विद्युत व यांत्रिकी विभाग

ई - कोटेशन नोटीस क्रं. ९ /२०२१-२२

**कामाचे नांव** : मनपाचे निलगिरीबाग जलशुद्धीकरण केंद्र येथे फ्लो मीटर करीता डाटा केबल पुरविणे, बसविणे व इतर कामे करणे

१. कामाची मुदत : ३० दिवस
२. कोटेशन फॉर्म मिळण्याचे ठिकाण : कार्यकारी अभियंता (यां.)  
राजीव गांधी भवन, नाशिक
३. काम करणेचे ठिकाण : विषयांकित
४. कोटेशन फॉर्म मिळण्याची तारीख : दि.२७/१२/२०२१ ते ३१/१२/२०२१
५. कोटेशन जमा करण्याचे ठिकाण : कार्यकारी अभियंता (यां.)  
राजीव गांधी भवन, नाशिक

सही/-  
कार्यकारी अभियंता (यां.)  
नाशिक महानगरपालिका