

नाशिक महानगर परिवहन महामंडळ लि. (सिटीलिनक)

अल्प मुदत ई – कोटेशन नोटीस क्र.०४/२०२६-२०२७

कामाचे नाव Annual maintenace contract of electrification, electrical panel and AC work at NMPML Citilinc Offices, Nashik.

- १) कोटेशन फॉर्म जमा करण्याचे ठिकाण : महाव्यवस्थापक (प्रशासन व तांत्रिकी)  
नामपमलि (सिटीलिनक)
- २) कोटेशन जमा करण्याची तारीख : दि. २९ / ०४ / २०२६ ते दि. ०६ / ०५ / २०२६  
सायं. ०५: ०० वाजेपर्यंत

**Commercial Bid: -**

S. N	Item	Qty	Per	Rate	Amount
1	Supplying and erecting PVC trunking (PVC casing-n-capping) of size 25mm with accessories on wall/ceiling (PWD DSR 2023-24, 1-2-7)	1	Mtr	38.00	38.00
2	Supplying and erecting mains with 2x1.5 sq.mm FRLSH copper PVC insulated wire laid in provided conduit 46/- + Earth wire 1x1.5 sqmm 23/- = 69/- (PWD DSR 2023-24, 1-3-1)	1	Mtr	69.00	69.00
3	Supplying and erecting mains with 2x2.5 sq.mm FRLSH copper PVC insulated wire laid in provided conduit 71/- + Earth wire 1x1.5 sqmm 23/- = 94/- (PWD DSR 2023-24, 1-3-2,1)	1	Mtr	94.00	94.00
4	Supplying & erecting mains with 3x4 sq.mm FRLSH copper PVC insulated wire laid in provided conduit/trunking/inside pole/bus bars or any other places (PWD DSR 2023-24, 1-3-7)	1	Mtr	149.00	149.00
5	Supplying and installing FR PVC sheathed HDPE insulated copper cat-6A cable suitable for networking compliant with ANSI/TIA-568.2-D standards in provided conduit/casing-n-capping (PWD DSR 2023-24, 19-3-3)	1	Mtr	73.00	73.00
6	Supplying, installing and testing UTP connector (RJ-45) (PWD DSR 2023-24, 19-5-74)	1	Nos	74.00	74.00
7	Supplying and erecting LED square / circular Max. 25 W down lighter / Panel Light having pressure die-cast aluminium housing, polystyrene diffuser having system lumens output of Min. 2750 Lumens, min. efficacy of 110 lumen CCT upto 6500K, p.f. >0.95, operating range of 120-270V including driver, having mounting arrangement with board for surface type or spring loaded mounting clips complete (PWD DSR 2023-24, 2-1-6)	1	Nos	1945.00	1945.00

S. N	Item	Qty	Per	Rate	Amount
8	Supplying and erecting anodized aluminium light LED fitting (4 feet) Max. 22W with high transitivity diffuser with system lumens output of Min.2200 lumens , min. efficacy of 100 lumen, CCT upto 6000K, p.f. >0.95, operating range of 200-270V, including driver with end caps on provided PVC Block/wooded board (PWD DSR 2023-24, 2-1-18)	1	Nos	802.00	802.00
9	Supplying and erecting integrated LED flood light fitting Max. 100W IP65 & IK07 class having pressure die-cast aluminium housing, having system lumens output of Min. 12000 Lumens, min. efficacy of 120 lumen/W, CRI>70, CCT upto 6500K, THD<10%, p.f. >0.90, operating range of 140-270V, inbuilt surge protection of 4 kV, Life class of 50,000 Hrs at L70B50 including driver with U shaped bracket with minimum 2 Years warranty (PWD DSR 2023-24, 2-3-15)	1	Nos	7576.00	7576.00
10	Supplying and erecting integrated LED street light fitting 70-75W IP65 & IK08 class having single piece pressure die-cast aluminium housing, having system lumens output of Min. 7700 Lumens, min. efficacy of 110 lumen/W, CCT upto 6500K, p.f. >0.95, operating range of 140-270V including driver complete with minimum 2 Years warranty (PWD DSR 2023-24, 2-3-6)	1	Nos	5753.00	5753.00
11	Supplying and erecting street light Wall bracket made from 25 mm. dia 'B' class G.I. pipe 1.2 m in total length complete (PWD DSR 2023-24, 2-6-3)	1	Nos	715.00	715.00
12	Supplying and erecting Energy Saving BLDC Ceiling fan 230 V A.C. 50 cycles 1200 mm, Max. Energy Consumption of 28W having service ratio (CMM/W) of Min. 8 , PF>0.9, THD<10% Temperature Rise of Max. 40 deg.C, having external mounted control PCB completely erected in position (PWD DSR 2023-24, 2-9-22, Note 1-4049/-)	1	Nos	4499.00	4499.00
13	Supplying and erecting exhaust fan medium duty 230 V A.C. 50 cycles 225 mm. 1400 RPM with condenser complete erected in position with necessary materials. Fan motor with moisture proof treatment and 'E' class insulation. (PWD DSR 2023-24, 2-10-13)	1	Nos	1701.00	1701.00
14	Supplying, erecting & marking SPMCB 40A, in provided distribution board (PWD DSR 2023-24, 5-3-4)	1	Nos	369.00	369.00
15	Supplying, erecting & marking DPMCB 40A, in provided distribution board (PWD DSR 2023-24, 5-3-8)	1	Nos	713.00	713.00
16	Supplying, erecting & marking FPMCB 40A to 63A in provided distribution board (PWD DSR 2022-23, 5-3-13)	1	Nos	1329.00	1329.00

S. N	Item	Qty	Per	Rate	Amount
17	Supplying and erecting single pole and neutral distribution board (SPNDB), with 2 ways for incoming and 2 ways (2 poles) for outgoing SP MCBs, with door, 1.2mm thickness surface/flush mounted, IP 43 Protection on provided iron/GI frame (PWD DSR 2023-24, 5-4-7)	1	Nos	818.00	818.00
18	Supplying & erecting triple pole and neutral distribution board (TPNDB), SP/TP MCBs total 4 ways/12 Poles, with door, 1.2mm thickness surface/flush mounted, IP 43 Protection on provided iron/GI frame (PWD DSR 2023-24, 5-4-4)	1	Nos	4582.00	4582.00
19	Supplying and erecting modular type switch 6A/10A on provided plate and box with wiring connections complete. (PWD DSR 2023-24, 1-6-1)	1	Nos	72.00	72.00
20	Supplying and erecting modular type switch 16/20 A with indicator on provided plate and box with wiring connections complete. (PWD DSR 2023-24, 1-6-6)	1	Nos	145.00	145.00
21	Supplying and erecting modular type 3 pin 6A multi socket with safety shutter on provided plate and box with wiring connections complete. (PWD DSR 2023-24, 1-6-10)	1	Nos	116.00	116.00
22	Supplying and erecting modular type 3 pin 6/16A multi socket with safety shutter on provided plate and box with wiring connections complete. (PWD DSR 2023-24, 1-6-11)	1	Nos	186.00	186.00
23	Supplying and erecting modular type blanking plate one module, on provided plate & box. (PWD DSR 2023-24, 1-6-24)	1	Nos	24.00	24.00
24	Supplying and erecting modular type computer Jack RJ 45 with safety shutter, on provided plate and box with wiring connections complete. (PWD DSR 2023-24, 1-6-17)	1	Nos	152.00	152.00
25	Supplying and erecting modular type electronic step regulator for fan two module ISI mark approved make duly erected on provided plate and box with wiring connections complete. (PWD DSR 2023-24, 1-6-23)	1	Nos	385.00	385.00
26	Supplying and erecting fan clamp of 30 x 5 mm. M.S. flat of required length and 10 mm. M.S. bolt and nuts erected with necessary hook of 10 mm. M.S. round bar and painted. (PWD DSR 2023-24, 2-10-3)	1	Nos	205.00	205.00
27	Supplying and erecting 'B' grade G.I. pipe / M.S. pipe down rod duly painted for fan complete erected (PWD DSR 2023-24, 2-10-6)	1	Nos	241.00	241.00
28	Supplying and erecting PVC Surface modular switch box with mounting plate for following modules complete. (PWD DSR 2023-24, 1-6-26 to 34)				0.00
29	1 module	1	Nos	141.00	141.00
30	2 module	1	Nos	143.00	143.00
31	3 module	1	Nos	168.00	168.00
32	4 module	1	Nos	196.00	196.00

S. N	Item	Qty	Per	Rate	Amount
33	6 module	1	Nos	252.00	252.00
34	8 module	1	Nos	311.00	311.00
35	12 module	1	Nos	391.00	391.00
36	16/18 module	1	Nos	450.00	450.00
37	Point wiring for light/bell/exhaust fan in PVC trunking (casing-capping) with 1.5 sq.mm (2+1E) copper wire, modular type switch, earthing and required accessories (PWD DSR 2023-24, 1-7-18)	1	Point	519.00	519.00
38	Point wiring for ceiling fan in PVC trunking (casing-capping) with 1.5 sq.mm (2+1E) copper wire, modular type switch, earthing and required accessories. (PWD DSR 2023-24, 1-7-19)	1	Point	571.00	571.00
39	Point wiring for independent plug in PVC trunking (casing-capping) with 1.5 sq.mm (2+1E) copper wire, modular type switch, earthing and required accessories (PWD DSR 2023-24, 1-7-20)	1	Point	719.00	719.00
40	Wiring for plug on board with switch socket surface/concealed type, copper wiring and earthing and with modular accessories (PWD DSR 2023-24, 1-7-25)	1	Point	397.00	397.00
41	Supplying and erecting electronic type cordless call bell having portable bell push working on 9V D.C. battery or push and bell on 250 V A.C. supply. (PWD DSR 2023-24, 2-2-5)	1	Nos	555.00	555.00
42	Supplying and erecting PVC insulated PVC round sheathed FR 1.5 sq.mm (30no. x 0.25mm dia.) 3 core flexible multi stranded copper industrial cable for voltage grade up to 1.1 kV (PWD DSR 2023-24, 1-3-14)	1	Mtr	70.00	70.00
43	Supplying and erecting mains with WP 2 x 6 sq. mm. 1.1kV. grade aluminium PVC insulated and PVC sheathed wires (PWD DSR 2023-24, 1-4-3)	1	Mtr	85.00	85.00
44	Supplying & erecting FRP box of size 300mm x 200mm x 125 mm, 2.7 mm thick complete on pole/wall (PWD DSR 2023-24, 7-8-10)	1	Nos	790.00	790.00
45	Carrying out core cutting of size 3" to 5" dia x 1" length in the C.C./rock/stone wall with the help of specialized core cutting machine in proper manner (3454/15" = 230/in) (PWD DSR 2023-24, 3-11-77)	1	In	230.00	230.00
46	Providing and fixing PVC insulated PVC round sheathed 2.5 sq.mm 3 core flexible multi stranded copper Industrial cable for voltage grade up to 1.1 kV (PWD DSR 2023-24, 1-3-15)	1	Mtr	111.00	111.00
47	Providing and fixing copper pipe suitable for refrigeration system having size 12 mm complete. (PWD DSR 2023-24, 3-2-26)	1	Mtr	304.00	304.00
48	Supplying and erecting stand for erecting outdoor unit of split type air conditioner complete.	1	Nos	4200.00	4200.00
49	Providing and fixing copper pipe suitable for refrigeration system having size 16 mm complete. (PWD DSR 2023-24, 3-2-27)	1	Mtr	454.00	454.00

S. N	Item	Qty	Per	Rate	Amount
50	Providing and fixing Elastomeric Nitrile rubber / foam tube type sleeves for over coating and insulating on provided copper pipes having sizes 12 mm (PWD DSR 2023-24, 4-2-3)	1	Mtr	77.00	77.00
51	Providing and fixing Elastomeric Nitrile rubber / foam tube type sleeves for over coating and insulating on provided copper pipes having sizes 16 mm (PWD DSR 2023-24, 4-2-4)	1	Mtr	86.00	86.00
52	Providing and fixing rigid PVC pipe 20 mm dia.with PVC accessories for drain (PWD DSR 2023-24, 1-2-3)	1	Mtr	84.00	84.00
53	Repairing in point wiring wiring for light fan instrument with ISI mark 2-1sq.mm, copper wire PVC insulated 1.1KV grade with necessary accessories as required complete.	1	Nos	238.00	238.00
54	Repairing in power point wiring with ISI mark 2-1.5 sq.mm, copper wire PVC insulated 1.1KV grade with necessary accessories as required complete.	1	Nos	378.00	378.00
55	Repairing of board with necessary accessories as required complete.	1	Nos	1195.00	1195.00
56	Providing annual comprehensive maintenance contract for split/window air conditioning unit complete as per terms and conditions. Job includes 1) servicing 2) on call repair 3) replacement of spares. The job excludes sheet metal work and plastic material. (PWD DSR 2023-24, 3-10-2,3,4)				
57	1 TR	1	Nos	7055.00	7055.00
58	1.5 TR	1	Nos	7838.00	7838.00
59	2 TR	1	Nos	9317.00	9317.00
60	Rewinding the motor of the all fan 1200 mm / 1400 mm of all types and makes and over hauling including minor repairs lubricating of ball bearings & bush bearing etc. & testing for original speed and consumption with replacing bearing (PWD DSR 2023-24,18-1-3,18-2-1)	1	Job	860.00	860.00
61	Providing replacement of unserviceable PCB for A/C unit upto 3 TR capacity. (PWD DSR 2023-24, 3-10-16)	1	Nos	5712.00	5712.00
62	Providing replacement of existing unserviceable rotary/scroll compressor of air conditioner upto 2 TR by new one of same capacity with guarantee for one year with provided refrigerant complete. (PWD DSR 2023-24, 3-10-8)	1	Nos	11762.00	11762.00
63	Providing vaccumising the airconditioner system to 200 micron and charging with R-410A/R32 refrigerant for air conditioning unit. (PWD DSR 2023-24, 3-10-24)	1	Kg	1182.00	1182.00
64	Supplying and erecting candle filter with filter pot for water cooler. (PWD DSR 2023-24, 3-10-36)	1	Nos	1440.00	1440.00

S. N	Item	Qty	Per	Rate	Amount
65	Supply, installation, testing and commissioning wireless remote control having colour LCD panel, real time clock, temperature limitation (16 to 30° C, functions like filter clean reminder timer suitable to communicate with wired controller complete. (PWD DSR 2023-24, 3-11-78)	1	Nos	1886.00	1886.00
66	Installing, testing & commissioning split type room air conditioning unit 1.3TR to 1.6TR capacity. (PWD DSR 2023-24, 3-2-11, 45399/- x 10% = 4540/-)	1	Nos	4540.00	4540.00
67	Installing, testing & commissioning split type room air conditioning unit 1.7TR to 2.0TR capacity. (PWD DSR 2023-24, 3-2-13, 67042/- x 10% = 6704/-)	1	Nos	6704.00	6704.00
68	Providing and erecting air circulator 450 mm. sweep oscillating type, wall mounting 1440 RPM without speed regulator, overheat protection unit, totally enclosed, flame proof motor suitable for 230/250 Volts single phase, 50 cycles A.C. supply, with one metre of 3core lead wire and with moisture proof treatment to winding and with 'E' class insulation. (PWD DSR 2023-24, 2-9-5)	1	Nos	4440.00	4440.00
69	Supplying pedestal type air circulator 450 mm. sweep oscillating type suitable to work on 230 Volts 50 cycles 1440 RPM without speed regulator, metallic blades, overheat protection unit, totally enclosed, flame proof motor with additional 3 core wire, 5 metre length and hand shield type 3 pin 5A. plug top complete with moisture proof treatment and 'E' class insulation. (PWD DSR 2023-24, 2-9-8)	1	Nos	4674.00	4674.00
70	Supplying and erecting 12V/42Ah SMF battery with battery terminal wire, duly charged complete (PWD DSR 2022-23, 3-8-10)	1	Nos	5425.00	5425.00
71	Supplying and erecting moulded case circuit breaker (MCCB)				
a	Up to 100A. (PWD DSR 2023-24, 5-5-1).	1	No	5808.00	5808.00
b	200A. (PWD DSR 2023-24, 5-5-3).	1	No	11092.00	11092.00
c	250A. (PWD DSR 2023-24, 5-5-4).	1	No	15858.00	15858.00
d	315/400A. (PWD DSR 2023-24, 5-5-6).	1	No	20209.00	20209.00
72	Supplying and erecting digital ammeter for measuring current (PWD DSR 2023-24, 6-5-7)	1	No	2135.00	2135.00
73	Supplying and erecting digital voltmeter for measuring voltage (PWD DSR 2023-24, 6-5-8).	1	No	1719.00	1719.00
74	Supplying and erecting multifunction meter (PWD DSR 2023-24, 6-5-14)	1	No	16271.00	16271.00
75	Supplying and erecting selector switches for voltmeter & ammeter (PWD DSR 2023-24, 6-7-1).	1	No	355.00	355.00
76	Supplying and erecting light emitting diode type indicator (PWD DSR 2023-24, 6-7-6)	1	No	421.00	421.00

