

नाशिक महानगरपालिका, नाशिक.
पाणीपुरवठा यांत्रिकी विभाग

ई-कोटेशन नोटीस क्र. ११ / २०२५-२६

कामाचे नाव :- मनपाचे गांधीनगर जलशुद्धीकरण केंद्र येथे ७५० केव्हीए ट्रान्सफॉर्मरची तातडीने
दुरुस्ती व अनुषंगिक कामे करणे बाबत.


१. कामाची मुदत :- ३ महिने

२. कोटेशन फॉर्म मिळण्याचे ठिकाण :- कार्यकारी अभियंता (यां)
राजीव गांधी भवन, मनपा, नाशिक.

३. काम करणेचे ठिकाण :- विषयांकित

४. कोटेशन जमा करण्याची अंतिम तारीख :- दि. २९ / ०३ / २०२६ ते दि. ^{०९}~~२९~~ / ०३ / २०२६

५. कोटेशन जमा करण्याचे ठिकाण :- कार्यकारी अभियंता (यां)
राजीव गांधी भवन, मनपा, नाशिक.



कार्यकारी अभियंता (यां)
मनपा नाशिक.

**NASHIK MUNICIPAL CORPORATION
WATER SUPPLY DEPARTMENT (MECH)
QUOTATION FORM**

Ref :- E-quotation No. :-

/2025-26

Abstract


Name of Work :- Rewinding, reconditioning and servicing of 750 KVA Transformer of Gandhinagar Water treatment plant, NMC.

S N	Item	Qty	Per	Rate	Amount
1	Inspection of distribution transformer on HV and LV side.	1	Job	4555.00	4555.00
2	Dismantling the distribution Transformer of 750KVA capacity from the plinth / foundation.	750	KVA	33.00	24750.00
3	Providing and filling Transformer oil.	100	Lit	144.00	14400.00
4	Painting of 11KV,750KVA transformer using smoke gray paint complete.	1	Job	3605.00	3605.00
5	Heating of core and winding, including removing of moisture etc complete	1	Job	9300.00	9300.00
6	Providing oil arresting sheet for low tension side of R Y B studs, 5mm thick properly fitted in the studs of transformer.	4	Nos	615.00	2460.00
7	Providing oil arresting sheet for top cover of oil chamber, LT connection box, oil tank etc parts, 5mm thick properly fitted in the top cover and nut bolts of transformer.	1	Set	3250.00	3250.00
8	Providing R Y B stud bushings over the oil arresting sheet on the studs of transformer .	7	Nos	355.00	2485.00
9	Providing HT side stud of transformer with insulator and accessories complete.	1	No	5950.00	5950.00
10	Providing and rewinding of copper material for HT/LT coils.	15	Kg	878.00	13170.00
11	Reinsulation by high quality uniform covering throughout of 11KV windings using accessories complete.	18	Coils	2850.00	51300.00
12	Reinsulation by high quality uniform covering throughout of 415V windings using accessories complete.	3	Coils	13750.00	41250.00
13	Repairing and servicing of tap changer of 11KV,750KVA transformer	1	No	2750.00	2750.00
14	Transformer oil filtration.	625	Ltr	36.00	22500.00

4					
1	Changing silica jel of breather and adding breather oil.	1	Job	1250.00	1250.00
5					
1	Loading, unloading and transportation of transformer.	2	Jobs	15000.00	30000.00
6					
1	Attendance, engineering charges for connection of HT/LT cables and giving satisfactory test & trials of transformer complete	1	Job	15000.00	15000.00
7					
				Total Rs	247975
				Add GST @ 18%	44636
				Total Rs	292611

I/We hereby agree to execute the above work at _____%
 (in words _____ percent)
 below/above the estimated rates.

Signature of Contractor
 With Stamp


 Executive Engineer
 Nashik Municipal Corporation