

नाशिक महानगर परिवहन महामंडळ लि. (सिटीलिक)

अल्प मुदत ई - कोटेशन नोटीस क्र.30/२०२५-२०२६

कामाचे नाव नाशिक महानगर परिवहन महामंडळ लि (सिटीलिक) कंपनीचे गोल्फ क्लब मैदान पेथील ऑफिस मधील वीज कामाचा वार्षिक दुरुस्ती व देखभाल करण्याकरिता मक्तेदाराची नेमणूक करणे बाबत

१) कोटेशन फॉर्म जमा करण्याचे ठिकाण : महाव्यवस्थापक (प्रशासन व तांत्रिकी)
नामपगलि (सिटीलिक)

२) कोटेशन जमा करण्याची तारीख : दि. 2४/०3/२०२६ ते दि. ०१/०४ /२०२६
सायं. ०५:०० वाजेपर्यंत

Commercial Bid: -

Sr. no	Item	Qty	Per	Per Rate	Rate (all taxes Inclusive Rate)	Remark
1	Supplying and erecting PVC trunking (PVC casing-n-capping) of size 25mm with accessories on wall/ceiling (PWD DSR 2023-24, 1-2-7)	1	Mtr			
2	Supplying and erecting mains with 2x1.5 sq.mm FRLSH copper PVC Insulated wire laid in provided conduit 46/- + Earth wire 1x1.5 sqmm 23/- = 69/- (PWD DSR 2023-24, 1-3-1)	1	Mtr			
3	Supplying and erecting mains with 2x2.5 sq.mm FRLSH copper PVC insulated wire laid in provided conduit 71/- + Earth wire 1x1.5 sqmm 23/- = 94/- (PWD DSR 2023-24, 1-3-2,1)	1	Mtr			
4	Supplying & erecting mains with 3x4 sq.mm FRLSH copper PVC Insulated wire laid in provided conduit/trunking/inside pole/bus bars or any other places (PWD DSR 2023-24, 1-3-7)	1	Mtr			
5	Supplying and installing FR PVC sheathed HDPE insulated copper cat-6A cable suitable for networking compliant with ANSI/TIA-568.2-D standards in provided conduit/casing-n-capping (PWD DSR 2023-24, 19-3-3)	1	Mtr			
6	Supplying, installing and testing UTP connector (RJ-45) (PWD DSR 2023-24, 19-5-74)	1	Nos			
7	Supplying and erecting LED square / circular Max. 25 W down lighter / Panel Light having pressure die-cast aluminum housing, polystyrene diffuser having system lumens output of Min. 2750 Lumens, min. efficacy of 110 lumen CCT upto 6500K, p.f. >0.95, operating range of 120-270V including driver, having mounting arrangement with board for surface type or spring loaded mounting clips complete (PWD DSR 2023-24, 2-1-6)	1	Nos			

Sr. no	Item	Qty	Per	Per Rate	Rate (all taxes Inclusive Rate)	Remark
8	Supplying and erecting anodized aluminium light LED fitting (4 feet) Max. 22W with high transitivity diffuser with system lumens output of Min.2200 lumens , min. efficacy of 100 lumen, CCT upto 6000K, p.f. >0.95, operating range of 200-270V, including driver with end caps on provided PVC Block/wooded board (PWD DSR 2023-24, 2-1-18)	1	Nos			
9	Supplying and erecting integrated LED flood light fitting Max. 100W IP65 & IK07 class having pressure die-cast aluminium housing, having system lumens output of Min. 12000 Lumens, min. efficacy of 120 lumen/W, CRI>70, CCT upto 6500K, THD<10%, p.f. >0.90, operating range of 140-270V, inbuilt surge protection of 4 kV, Life class of 50,000 Hrs at L70B50 including driver with U shaped bracket with minimum 2 Years warranty (PWD DSR 2023-24, 2-3-15)	1	Nos			
10	Supplying and erecting integrated LED street light fitting 70-75W IP65 & IK08 class having single piece pressure die-cast aluminium housing, having system lumens output of Min. 7700 Lumens, min. efficacy of 110 lumen/W, CCT upto 6500K, p.f. >0.95, operating range of 140-270V including driver complete with minimum 2 Years warranty (PWD DSR 2023-24, 2-3-6)	1	Nos			
11	Supplying and erecting street light Wall bracket made from 25 mm. dia 'B' class G.I. pipe 1.2 m in total length complete (PWD DSR 2023-24, 2-6-3)	1	Nos			
12	Supplying and erecting Energy Saving BLDC Ceiling fan 230 V A.C. 50 cycles 1200 mm, Max. Energy Consumption of 28W having service ratio (CMM/W) of Min. 8 , PF>0.9, THD<10% Temperature Rise of Max. 40 deg.C, having external mounted control PCB completely erected in position (PWD DSR 2023-24, 2-9-22, Note 1-4049/-)	1	Nos			
13	Supplying and erecting exhaust fan medium duty 230 V A.C. 50 cycles 225 mm. 1400 RPM with condenser complete erected in position with necessary materials. Fan motor with moisture proof treatment and 'E' class insulation. (PWD DSR 2023-24, 2-10-13)	1	Nos			
14	Supplying, erecting & marking SPMCB 40A, in provided distribution board (PWD DSR 2023-24, 5-3-4)	1	Nos			
15	Supplying, erecting & marking DPMCB 40A, in provided distribution board (PWD DSR 2023-24, 5-3-8)	1	Nos			
16	Supplying, erecting & marking FPMCB 40A to 63A in provided distribution board (PWD DSR 2022-23, 5-3-13)	1	Nos			

Sr. no	Item	Qty	Per	Per Rate	Rate (all taxes Inclusive Rate)	Remark
17	Supplying and erecting single pole and neutral distribution board (SPNDB), with 2 ways for incoming and 2 ways (2 poles) for outgoing SP MCBs, with door, 1.2mm thickness surface/flush mounted, IP 43 Protection on provided iron/GI frame (PWD DSR 2023-24, 5-4-7)	1	Nos			
18	Supplying & erecting triple pole and neutral distribution board (TPNDB), SP/TP MCBs total 4 ways/12 Poles, with door, 1.2mm thickness surface/flush mounted, IP 43 Protection on provided iron/GI frame (PWD DSR 2023-24, 5-4-4)	1	Nos			
19	Supplying and erecting modular type switch 6A/10A on provided plate and box with wiring connections complete. (PWD DSR 2023-24, 1-6-1)	1	Nos			
20	Supplying and erecting modular type switch 16/20 A with indicator on provided plate and box with wiring connections complete. (PWD DSR 2023-24, 1-6-6)	1	Nos			
21	Supplying and erecting modular type 3 pin 6A multi socket with safety shutter on provided plate and box with wiring connections complete. (PWD DSR 2023-24, 1-6-10)	1	Nos			
22	Supplying and erecting modular type 3 pin 6/16A multi socket with safety shutter on provided plate and box with wiring connections complete. (PWD DSR 2023-24, 1-6-11)	1	Nos			
23	Supplying and erecting modular type blanking plate one module, on provided plate & box. (PWD DSR 2023-24, 1-6-24)	1	Nos			
24	Supplying and erecting modular type computer Jack RJ 45 with safety shutter, on provided plate and box with wiring connections complete. (PWD DSR 2023-24, 1-6-17)	1	Nos			
25	Supplying and erecting modular type electronic step regulator for fan two module ISI mark approved make duly erected on provided plate and box with wiring connections complete. (PWD DSR 2023-24, 1-6-23)	1	Nos			
26	Supplying and erecting fan clamp of 30 x 5 mm. M.S. flat of required length and 10 mm. M.S. bolt and nuts erected with necessary hook of 10 mm. M.S. round bar and painted. (PWD DSR 2023-24, 2-10-3)	1	Nos			
27	Supplying and erecting 'B' grade G.I. pipe / M.S. pipe down rod duly painted for fan complete erected (PWD DSR 2023-24, 2-10-6)	1	Nos			

Sr. no	Item	Qty	Per	Per Rate	Rate (all taxes Inclusive Rate)	Remark
28	Supplying and erecting PVC Surface modular switch box with mounting plate for following modules complete. (PWD DSR 2023-24, 1-6-26 to 34)					
29	1 module	1	Nos			
30	2 module	1	Nos			
31	3 module	1	Nos			
32	4 module	1	Nos			
33	6 module	1	Nos			
34	8 module	1	Nos			
35	12 module	1	Nos			
36	16/18 module	1	Nos			
37	Point wiring for light/bell/exhaust fan in PVC trunking (casing-capping) with 1.5 sq.mm (2+1E) copper wire, modular type switch, earthing and required accessories (PWD DSR 2023-24, 1-7-18)	1	Point			
38	Point wiring for ceiling fan in PVC trunking (casing-capping) with 1.5 sq.mm (2+1E) copper wire, modular type switch, earthing and required accessories. (PWD DSR 2023-24, 1-7-19)	1	Point			
39	Point wiring for independent plug in PVC trunking (casing-capping) with 1.5 sq.mm (2+1E) copper wire, modular type switch, earthing and required accessories (PWD DSR 2023-24, 1-7-20)	1	Point			
40	Wiring for plug on board with switch socket surface/concealed type, copper wiring and earthing and with modular accessories (PWD DSR 2023-24, 1-7-25)	1	Point			
41	Supplying and erecting electronic type cordless call bell having portable bell push working on 9V D.C. battery or push and bell on 250 V A.C. supply. (PWD DSR 2023-24, 2-2-5)	1	Nos			
42	Supplying and erecting PVC insulated PVC round sheathed FR 1.5 sq.mm (30no. x 0.25mm dia.) 3 core flexible multi stranded copper industrial cable for voltage grade up to 1.1 kV (PWD DSR 2023-24, 1-3-14)	1	Mtr			

Sr. no	Item	Qty	Per	Per Rate	Rate (all taxes Inclusive Rate)	Remark
43	Supplying and erecting mains with WP 2 x 6 sq. mm. 1.1kV. grade aluminium PVC insulated and PVC sheathed wires (PWD DSR 2023-24, 1-4-3)	1	Mtr			
44	Supplying & erecting FRP box of size 300mm x 200mm x 125 mm, 2.7 mm thick complete on pole/wall (PWD DSR 2023-24, 7-8-10)	1	Nos			
45	Carrying out core cutting of size 3" to 5" dia x 1" length in the C.C./rock/stone wall with the help of specialized core cutting machine in proper manner (3454/15" = 230/in) (PWD DSR 2023-24, 3-11-77)	1	In			
46	Providing and fixing PVC insulated PVC round sheathed 2.5 sq.mm 3 core flexible multi stranded copper Industrial cable for voltage grade up to 1.1 kV (PWD DSR 2023-24, 1-3-15)	1	Mtr			
47	Providing and fixing copper pipe suitable for refrigeration system having size 12 mm complete. (PWD DSR 2023-24, 3-2-26)	1	Mtr			
48	Supplying and erecting stand for erecting outdoor unit of split type air conditioner complete.	1	Nos			
49	Providing and fixing copper pipe suitable for refrigeration system having size 16 mm complete. (PWD DSR 2023-24, 3-2-27)	1	Mtr			
50	Providing and fixing Elastomeric Nitrile rubber / foam tube type sleeves for over coating and insulating on provided copper pipes having sizes 12 mm (PWD DSR 2023-24, 4-2-3)	1	Mtr			
51	Providing and fixing Elastomeric Nitrile rubber / foam tube type sleeves for over coating and insulating on provided copper pipes having sizes 16 mm (PWD DSR 2023-24, 4-2-4)	1	Mtr			
52	Providing and fixing rigid PVC pipe 20 mm dia.with PVC accessories for drain (PWD DSR 2023-24, 1-2-3)	1	Mtr			
53	Repairing in point wiring wiring for light fan instrument with ISI mark 2-1sq.mm, copper wire PVC insulated 1.1KV grade with necessary accessories as required complete.	1	Nos			
54	Repairing in power point wiring with ISI mark 2-1.5 sq.mm, copper wire PVC insulated 1.1KV grade with necessary accessories as required complete.	1	Nos			
55	Repairing of board with necessary accessories as required complete.	1	Nos			

Sr. no	Item	Qty	Per	Per Rate	Rate (all taxes Inclusive Rate)	Remark
56	Providing annual comprehensive maintenance contract for split/window air conditioning unit complete as per terms and conditions. Job includes 1) servicing 2) on call repair 3) replacement of spares. The job excludes sheet metal work and plastic material. (PWD DSR 2023-24, 3-10-2,3,4)					
57	1 TR	1	Nos			
58	1.5 TR	1	Nos			
59	2 TR	1	Nos			
60	Rewinding the motor of the all fan 1200 mm / 1400 mm of all types and makes and over hauling including minor repairs lubricating of ball bearings & bush bearing etc. & testing for original speed and consumption with replacing bearing (PWD DSR 2023-24,18-1-3,18-2-1)	1	Job			
61	Providing replacement of unserviceable PCB for A/C unit upto 3 TR capacity. (PWD DSR 2023-24, 3-10-16)	1	Nos			
62	Providing replacement of existing unserviceable rotary/scroll compressor of air conditioner upto 2 TR by new one of same capacity with guarantee for one year with provided refrigerant complete. (PWD DSR 2023-24, 3-10-8)	1	Nos			
63	Providing vaccumising the airconditioner system to 200 micron and charging with R-410A/R32 refrigerant for air conditioning unit. (PWD DSR 2023-24, 3-10-24)	1	Kg			
64	Supplying and erecting candle filter with filter pot for water cooler. (PWD DSR 2023-24, 3-10-36)	1	Nos			
65	Supply, installation, testing and commissioning wireless remote control having colour LCD panel, real time clock, temperature limitation (16 to 30° C, functions like filter clean reminder timer suitable to communicate with wired controller complete. (PWD DSR 2023-24, 3-11-78)	1	Nos			
66	Installing, testing & commissioning split type room air conditioning unit 1.3TR to 1.6TR capacity. (PWD DSR 2023-24, 3-2-11, 45399/- x 10% = 4540/-)	1	Nos			
67	Installing, testing & commissioning split type room air conditioning unit 1.7TR to 2.0TR capacity. (PWD DSR 2023-24, 3-2-13, 67042/- x 10% = 6704/-)	1	Nos			

Sr. no	Item	Qty	Per	Per Rate	Rate (all taxes Inclusive Rate)	Remark
68	Providing and erecting air circulator 450 mm. sweep oscillating type, wall mounting 1440 RPM without speed regulator, overheat protection unit, totally enclosed, flame proof motor suitable for 230/250 Volts single phase, 50 cycles A.C. supply, with one metre of 3core lead wire and with moisture proof treatment to winding and with 'E' class insulation. (PWD DSR 2023-24, 2-9-5)	1	Nos			
69	Supplying pedestal type air circulator 450 mm. sweep oscillating type suitable to work on 230 Volts 50 cycles 1440 RPM without speed regulator, metallic blades, overheat protection unit, totally enclosed, flame proof motor with additional 3 core wire, 5 metre length and hand shield type 3 pin 5A. plug top complete with moisture proof treatment and 'E' class insulation. (PWD DSR 2023-24, 2-9-8)	1	Nos			
70	Supplying and erecting 12V/42Ah SMF battery with battery terminal wire, duly charged complete (PWD DSR 2022-23, 3-8-10)	1	Nos			
71	Supplying and erecting moulded case circuit breaker (MCCB)					
a	Up to 100A. (PWD DSR 2023-24, 5-5-1).	1	No			
b	200A. (PWD DSR 2023-24, 5-5-3).	1	No			
c	250A. (PWD DSR 2023-24, 5-5-4).	1	No			
d	315/400A. (PWD DSR 2023-24, 5-5-6).	1	No			
72	Supplying and erecting digital ammeter for measuring current (PWD DSR 2023-24, 6-5-7)	1	No			
73	Supplying and erecting digital voltmeter for measuring voltage (PWD DSR 2023-24, 6-5-8).	1	No			
74	Supplying and erecting multifunction meter (PWD DSR 2023-24, 6-5-14)	1	No			
75	Supplying and erecting selector switches for voltmeter & ammeter (PWD DSR 2023-24, 6-7-1).	1	No			
76	Supplying and erecting light emitting diode type indicator (PWD DSR 2023-24, 6-7-6)	1	No			
77	Supplying and erecting L.T. Current transformer of suitable ratio (PWD DSR 2023-24, 6-7-2)	1	No			

Sr. no	Item	Qty	Per	Per Rate	Rate (all taxes Inclusive Rate)	Remark
78	Supplying and erecting iron work, sheet metal work consisting of CRCA sheets, various sections of iron, plates, chequered plates, rods, bars, MS pipes, etc. for panel board or any other purpose with bending, cutting, drilling and welding complete erected at the position with necessary materials (PWD DSR 2023-24, 6-1-19)	1	Kg			

Technical Bid -

- 1) MSME Certificate
- 2) Pan card
- 3) Aadhaar Card
- 4) GST Registration Certificate
- 5) Work Completion Certificate

Note :- १) Technical Bid व Commercial Bid स्वतंत्र दोन लिफाफा मध्ये सादर करणे.

२) निवड झालेल्या मक्तेदाराला अटी व शर्ती र.रु ५००/- च्या स्टॅम्प पेपर वर देणे आवश्यक आहे.

३) कोटेशन/निविदा रक्कमेच्या ३% इतकी रक्कम सुरक्षा अनामत म्हणून Demand Draft (D.D.) स्वरूपात जमा करणे बंधनकारक राहिल. सदर मक्तेदारासोबत करण्यात आलेला करार संपुष्टात आल्यानंतर, अटी व शर्तीचे पालन झाल्यास, जमा केलेली ३% सुरक्षा अनामत रक्कम मक्तेदारास परत करण्यात येईल.



महाव्यवस्थापक (प्रशासन व तांत्रिकी)
नाशिक महानगर परिवहन महामंडळ लि. (सिटीलिक)