

नाशिक महानगरपालिका, नाशिक

मलनिःसारण यांत्रिकी विभाग

ई-कोटेशन नोटीस क्रमांक ०१ / २०२२ -२३

**कामाचे नाव :-** मनपाचे पंचक मलनिःसारण केंद्र येथील कार्यालयीन इमारतीचे  
वाँटर प्रूफिंग व ईतर कामे करणेबाबत.

१. कामाची मुदत :- २ महिने
२. कोटेशन फॉर्म मिळण्याचे ठिकाण :- कार्यकारी अभियंता(यां) ,  
राजीव गांधी भवन, म.न.पा. नाशिक
३. काम करणेचे ठिकाण :- विषयांकित
४. कोटेशन फॉर्म मिळण्याची तारीख :- दिनांक ४/१०/२०२२ ते १०/१०/२०२२
५. कोटेशन जमा करण्याची अंतिम तारीख :- ११/१०/२०२२ दुपारी १.०० वाजेपर्यंत
६. कोटेशन जमा करण्याचे ठिकाण :- कार्यकारी अभियंता(यां) ,  
राजीव गांधी भवन, म.न.पा. नाशिक

Sd/-

कार्यकारी अभियंता(यां) ,  
नाशिक महानगरपालिका, नाशिक

**NASHIK MUNICIPAL CORPORATION  
WATER SUPPLY DEPARTMENT (MECH)**

Date:

**Name of work;**-Providing and fixing water proofing on office building slab and allied works at panchak

Name of Contractoer : M/s

Estimate Cost : Rs.298639/-

Sr No	Description	Qty	Unit	Rate	Amount
1	Providing & Fixing in position, 12mm wp Plywood & 1.5mm laminate panel above the fabricated frame on one side, as per Architectural & Acoustical Design & Instructions & Complete in all aspects. including all materials labour, finishing etc complete	18	Sq M	3170	57060
2	Providing & Fixing in position, MS fabrication work using angles, sq tubes, c channel set for various partition frame as per Design & Instructions & Complete in all aspects. including all materials labour, finishing etc complete	166.55	Kg	85	14156
3	Water proofing Treatment to existing Terrace by using Polymeric cementitious membrane of approved make & approved by Engineer in charge by replacing the existing water proofing treatment. Break open the existing I.P.S. and brick bat coba of the terraces lab to expose the bare slab. (If there are cracks on the bare slab open the crack in V Groove and fill it with P.M.M. and if there are lots of honeycombs and identified bad patches of concrete the same should be grouted by grouting procedures). Clean the entire surface thoroughly and over this prepared surface, apply three coats of polymeric water proofing coating having a breathable non toxic acrylic polymer liquid of approved make & approved by Engineer in charge, over this water proofing treatment, provide and lay brick bat coba of average 112 mm thickness	98.7	Sq M	1980	195426
		Total			266642
		Add GST 12%			31997
		<b>Total</b>			<b>298639</b>

I/we are hereby agree to execute the above work at \_\_\_\_%. In ( ) words \_\_\_\_\_ (above/below) the estimated rates only.

Contractor

Sd/-  
Executive Engineer (Mech)  
Nashik Municipal Corporation