

नाशिक महानगरपालिका, नाशिक

ई - कोटेशन नोटीस क्र. ०८

दि.२२/११/२०२२

नाशिक महानगरपालिका सार्वजनिक आरोग्य विभागांतर्गत जे.डी.सी. बिटको रुग्णालय, नाशिकरोड येथील X-Ray DR System मशिन हिंदू हृदयसम्राट मा.बाळासाहेब ठाकरे रुग्णालय, नाशिकरोड (नवीन बिटको रुग्णालय) येथे स्थलांतर करणे कामी जाहीर ई-कोटेशन दर मागविणेत येत आहेत.

१. कोटेशन फॉर्म मिळण्याचा कालावधी : २२/११/२०२२ ते २९/११/२०२२

२. कोटेशन फॉर्म भरून जमा करणेची अंतिम तारीख : २९/११/२०२२

३. कोटेशन फॉर्म मिळण्याचे ठिकाण व वेळ : वैद्यकिय (आरोग्य) अधिकारी कार्यालय,  
राजीव गांधी भवन, ३रा मजला, शरणपुर  
रोड, नाशिक.  
वेळ : सकाळी १०:०० ते ४:०० पर्यंत.  
संकेतस्थळ : nmc.gov.in

कोटेशन फॉर्म पूर्ण भरून बंद लिफाफ्यात मा.वैद्यकिय (आरोग्य) अधिकारी यांचे नावे मनपा राजीव गांधी भवन, सार्वजनिक आरोग्य विभाग येथे कार्यालयीन वेळेत देण्यात यावे. अपूर्ण कोटेशन स्विकारले जाणार नाही. कोटेशन फॉर्म सोबत पॅन कार्ड व जी.एस.टी.रजि.प्रमाणपत्र जोडणे अनिवार्य आहे. कोटेशन फॉर्म स्विकारण्याचा अथवा नाकारण्याचा हक्क राखून ठेवण्यात आला आहे.

Sd/-

वैद्यकिय (आरोग्य) अधिकारी  
नाशिक महानगरपालिका, नाशिक.



**नाशिक महानगरपालिका, नाशिक**  
**कोटेशन फॉर्म**

**दि : २२/११/२०२२**

निम्नलिखित तपशिला प्रमाणे, नाशिक महानगरपालिका सार्वजनिक आरोग्य विभागांतर्गत जे.डी.सी. बिको रुग्णालय, नाशिकरोड येथील X-Ray DR System मशिन हिंदू हृदयसम्राट मा.बाळासाहेब ठाकरे रुग्णालय, नाशिकरोड (नवीन बिको रुग्णालय) येथे स्थलांतर करणे कामी बाजारभाव (Quotation) बोलविणेत येत आहेत. तरी त्याबाबतचे दर बंद पाकिटातून दिनांक २९/११/२०२२ पर्यंत इकडील कार्यालयात पाठविण्याचे करावे.

सदरचे दर पुरवठादारास सन २०२२-२३ या वर्षासाठी बंधनकारक राहतील. दर हे सर्व करांसहीत सादर करावेत.

| (A) Scope of work for Turnkey work (Civil Work) for shifting of Digital Radiography System(X-ray D.R.System)<br>(Model-ProRad 2FC with Detector bearing serial no.A60-AT/B17/009) |  |               |   |
|---|--|---------------|---|
| SR NO   | WORK DESCRIPTION   | Qty. in Sq.ft | RATE<br>(Total Amount Including of all taxes) |
| 1   | Chipping, Breaking, removing and disposing off demolition material away from the site like flooring, skirting etc. complete as per the requirements.   | 262.03        |   |
| 2   | Providing and constructing 9" thick walls using quality table mould bricks and plastering on both side as per the design and drawing in CM 1:6 as per the specification including scaffolding, curing, cleaning etc. complete with lime finish | 569.45        |   |
| 3   | Providing Flore Concreting as PCC works for Table and Chest Stand  | 62.00         |   |
| 4   | Providing and laying 600x600 mm approved make and shade vitrified tiles of standard company for the flooring on a bed of 20 mm CM 1:6 and cement slurry and the joints filled with matching grouting etc.                                      | 262.03        |   |
| 5   | Do as above for the wall cladding upto 6 FT height of vitrified tiles of standard company.   | 543.93        |   |
| 6   | Providing and fixing Sal wood frame of size 5" x 3" and 30 mm thick water proof shutter for the doors including necessary fittings and fixtures as per the requirements and specifications with Lead sheet etc.                                | 61.69         |   |
| 7   | Carpentry work for the paneling and lead glass fixing with lead sheet as per the requirements(4 X 6)= 16 RFT   | 16.00         |   |
| 8   | Providing and fixing automatic door closers as standard Hydraulic system   | 3.00          |   |
| 9   | Providing Sliding window for   | 18.00         |   |

|    |   |        |  |
|----|---|--------|--|
|    | counter in Console room for Registration desk   |        |  |
| 10 | Copper Earthing Work.- Earthing installation minimum depth of 2.5 mtrs below ground level after preparation of ground with charcoal, sand and salt. connecting the 8g copper lead in strip by bolting and brazing to the copper plate complete with brass bolt of suitable length double nuts and washer including supply and fixing of 50mm dia 2.3.mtr long GI Pipe with funnel for watering arrangement complete in all respects(15 mtr) | 1.00   |  |
| 11 | Providing and Fixing electrical conduct wire ,modular switches, Ceiling Lights 2x2=6 nos. of standard certified company as per the requirements and drawings.( Upto 25 Points for Power Supply and as per specifications. All the electrical work should be concealed   | 1.00   |  |
| 12 | 6"x6" Electrical casing/ Trench work for electric cabling work in the flooring as per the drawings. ( 54 ft Length)   | 54     |  |
| 13 | Providing and fixing Gypsum Board false ceiling for the room as per the requirement and specification of make Reliance etc.complete Required in DR & Console Room only  | 262.03 |  |
| 14 | Painting for the internal and external walls,ceiling and door with necessary putty works as per the requirement with Plastic emulsion paint of standard certified company for the complete walls etc.   | 882.72 |  |

| B) Scope of work for De Commissioning,shifting and ReCommissioning of Digital Radiography System(X-ray D.R.System)<br>(Model-ProRad 2FC with Detector bearing serial no.A60-AT/B17/009) |   |      |   |
|---|---|------|---|
| SR NO   | WORK DESCRIPTION  | Qty. | RATE<br>(Total Amount Including of all taxes) |
| 1   | De Commissioning:Rails, Carriage Telescope, X-Ray tube Column, HT cable hose routing. Wall stand, Digital flat panel detector. Console panel systems.<br><u>Shifting of equipment from one Hospital to another Hospital:</u><br>Re Commissioning: Fixing rails, carriage bridge. telescope. X-Ray tube, Column, HT cable hose routing, wall stand, Digital flat panel detector. Console panel systems. Recalibration of the entire system.<br><u>QA Testing after Re commissioning:</u> | 1 No |   |
| A + B = Total Amount  |   |      |   |

पुरवठादाराची सही व शिक्का