

Nashik Municipal Corporation,Nashik PWD Department (Trafic Cell) Quotation form Name of Work- Provinding Fixing and Remoing on Rental basic Temporay Nivara Shed, Stall, colak Room, Bhavik gram, (German Hanger), Stell Table, PVC Chair, at innar Parking and outer parking Shimastha kumbh Mela 2026-27 NMC Nashik. Date Of Issue of Blank Quotation Form - 12/11/2025 TO 19/11/2025. Date Of Submission Quotation Form - 19/11/2025. UP TO 03.00 PM ABSTRACT			
Quotation for Nashik Shimastha Kumbha Mela 2026			
No.	Item Description	Unit	Rate
1	Temporary Nirvana Shed size of 20 mtr x 25 Mtr		
	Providing, erecting & maintaining of C.G.I Sheet temporary shed of various size on 75 mm (3") diameter mild steel pipe column at distance of 4.50mt (15' 0")from centre to centre in width & 3.60 mt (12'0") in length as per detailed drawing with 65 mm (2' 1/2") diameter M.S Pipes rafters at a distance of 3.60 mt (2'0") Centre to centre purlin fixed with 50 mm (2") diameter M.S pipe at a distance of 350mt (4'6") with necessary clamp nut bolts etc. to make the structure strong to support the load of C.G.I sheet. The roof cladding will be made with leek proof C.G.I Sheet without imperfection or hole which will be fixed with iron "Z" shape clamps/ hooks etc. Three sides of shed/hutt accommodation will be covered with G,I sheets walling. All the exposed surface of M.S pipes, will be painted with good quality enamel paints. All material including M.s pipe G.I sheet etc. will be supplied by the contractor and after Kumbh Mela (2 months) material will be taken back by the contractor. During above period of Kumbh Mela contractor has to maintain and preserve as well as upkeep the structure of temporary shed by employing his own labour with watch and word etc complete. The above structure will be above plinth only and on rental basis.	Per Sqm for 1 Month	
	Providing, supplying & fixing cloth ceiling inside the shed structure on wooden section framework/steel framework of 50x65mm wooden sections. All material will be supplied by contractor & on rental basis. and after kumbhamela period removing the structure, cleaning the site & conveying the material and will be taken back by the contractor. Note: During period of kumbhamela contractor has to maintain and preserve as well as upkeep the structure of temporary by		
	Providing & Fixing of fascia 1.20mt height Front side of the shed made using CGI Sheet covered with good quality cloth		
	Providing Branding with good quality flex printing, MS Pipe framing, mounting & Installation on TOP Front Side fascia of Tin Shed size of 20 mtr x 1.20 mtr		
	Flooring:- Providing & fixing levelled flooring with 19mm block board fixed on wooden sections supports		
	Providing, supplying & fixing synthetic Needle Punch Carpet Flooring fixed/pasted on wooden floor or laid on ground. All material will be supplied by contractor & on rental basis. and after kumbhamela period removing the structure, cleaning the site & conveying the material and will be taken back by the contractor. Note: During period of kumbhamela contractor has to maintain and preserve as well as upkeep the structure of temporary by employing his own labour with watch and word etc. Completed as directed by engineer in charge.		
	Electrification :- Cabling & wiring of the entire structure along with providing electrical fixtures such as Ceiling fans 12 nos, Tube lights 12 no(Electrical power source near the shed will be provided by NMC)		

No.	Item Description	Unit	Rate
	Providing, supplying & fixing CGI Walling Covered with cloth inside & outside the shed structure on wooden section framework/steel framework of 50x65mm wooden sections. All material will be supplied by contractor & on rental basis. and after kumbhamela period removing the structure, cleaning the site & conveying the material and will be taken back by the contractor. Note: During period of kumbhamela contractor has to maintain and preserve as well as upkeep the structure of temporary by employing his own labour with watch and word etc. Completed as directed by engineer in charge.		
2	STALL SIZE OF 5 Mtr x 5 Mtr		
	Providing, erecting and maintain temporary pagoda shaped tents made of white fire retardant and waterproof PVC fabric covers for roof and walls on Aluminium Framework. Each Pagoda unit size is 5M x 5M. Minimum side height of the pagoda structure to be 2.5M. All Sides and roofing is to be covered/closed using premium grade, high gloss white, PVC coated polyester fabric - UV resistant, fire retardant and waterproof. Framework of pagoda to be made using hard pressed extruded structural aluminium, all connecting components of the aluminium framework should be of structural grade corrosive resistant galvanised steel. Main Aluminium Extrusion profile size should not be less than 63mm/63mm/2mm. All material will be supplied by contractor & on rental basis. and after kumbhamela period removing the structure, cleaning the site & conveying the material and will be taken back by the contractor. Note: During period of kumbhamela contractor has to maintain and preserve as well as upkeep the structure of temporary by employing his own labour with watch and word etc. Completed as directed by engineer in charge.	Per Sqm for 1 Month	
	Providing, supplying & fixing CGI Walling Covered with cloth inside & outside the shed structure on wooden section framework/steel framework of 50x65mm wooden sections. All material will be supplied by contractor & on rental basis. and after kumbhamela period removing the structure, cleaning the site & conveying the material and will be taken back by the contractor. Note: During period of kumbhamela contractor has to maintain and preserve as well as upkeep the structure of temporary by employing his own labour with watch and word etc. Completed as directed by engineer in charge.		
	Furniture & furnishing:- In padded cushion chairs -4 Nos. & Table With Frill -4 Nos., Spot/ tube light - 2 Nos & plug point - 2 Nos.		
	Flooring:- Providing & fixing levelled flooring with 19mm block board fixed on wooden sections supports		

No.	Item Description	Unit	Rate
	Providing, supplying & fixing synthetic Needle Punch Carpet Flooring fixed/pasted on wooden floor or laid on ground. All material will be supplied by contractor & on rental basis. and after kumbhamela period removing the structure, cleaning the site & conveying the material and will be taken back by the contractor. Note: During period of kumbhamela contractor has to maintain and preserve as well as upkeep the structure of temporary by employing his own labour with watch and word etc. Completed as directed by engineer in charge.		
	Electrification :- Cabling & wiring of the stall (Electrical power source near the shed will be provided by NMC)		
3	CLOAK ROOM SIZE OF 15 M X 20 M	Unit	Rate
	Providing, erecting & maintaining of C.G.I Sheet temporary shed of various size on 75 mm (3") diameter mild steel pipe column at distance of 4.50mt (15' 0")from centre to centre in width & 3.60 mt (12'0") in length as per detailed drawing with 65 mm (2' 1/2") diameter M.S Pipes rafters at a distance of 3.60 mt (2'0") Centre to centre purlin fixed with 50 mm (2") diameter M.S pipe at a distance of 350mt (4'6") with necessary clamp nut bolts etc. to make the structure strong to support the load of C.G.I sheet. The roof cladding will be made with leak proof C.G.I Sheet without imperfection or hole which will be fixed with iron "Z" shape clamps/ hooks etc. Three sides of shed/hutt accommodation will be covered with G,I sheets walling. All the exposed surface of M.S pipes, will be painted with good quality enamel paints. All material including M.s pipe G.I sheet etc. will be supplied by the contractor and after Kumbh Mela (2 months) material will be taken back by the contractor. During above period of Kumbh Mela contractor has to maintain and preserve as well as upkeep the structure of temporary shed by employing his own labour with watch and word etc complete. The above structure will be above plinth only and on rental basis.	Per Sqm for 1 Month	
	Providing, supplying & fixing cloth ceiling inside the shed structure on wooden section framework/steel framework of 50x65mm wooden sections. All material will be supplied by contractor & on rental basis. and after kumbhamela period removing the structure, cleaning the site & conveying the material and will be taken back by the contractor. Note: During period of kumbhamela contractor has to maintain and preserve as well as upkeep the structure of temporary by employing his own labour with watch and word etc. Completed as directed by engineer in charge.		
	Providing & Fixing of fascia 1.20mt height Front side of the shed made using CGI Sheet covered with good quality cloth		
	Flooring:- Providing & fixing levelled flooring with 19mm block board fixed on wooden		
	Providing, supplying & fixing synthetic Needle Punch Carpet Flooring fixed/pasted on wooden floor or laid on ground. All material will be supplied by contractor & on rental basis. and after kumbhamela period removing the structure, cleaning the site & conveying the material and will be taken back by the contractor. Note: During period of kumbhamela contractor has to maintain and preserve as well as upkeep the structure of temporary by employing his own labour with watch and word etc. Completed as directed by engineer in charge.		

No.	Item Description		
	Electrification :- Cabling & wiring of the of the entire structure along with providing electrical fixtures such as Ceiling fans 14 nos, LED lights 12 nos plug points.(Electrical power source near the shed will be provided by NMC)		
	Furniture & furnishing:- In Clock Room padded cushion chairs -4 Nos. & Table With Frill -4 Nos., Steel Rack - 2 Nos.		
4	BHAVIK GAM SIZE OF 30 M X 30 M (German Hanger)		
	Providing, erecting and maintain temporary Tent 40M/30M/25M/23M wide German Hanger/Marquee made of Aluminium Framework Pillar less with fire Retardant and waterproof PVC blackout covering as per DIN4102B1, BS5438/7837. Structure conforms to Industries Norms(DIN4112) for temporary buildings. . All material will be supplied by contractor & on rental basis. and after kumbhamela period removing the structure, cleaning the site & conveying the material and will be taken back by the contractor. Note: During period of kumbhamela contractor has to maintain and preserve as well as upkeep the structure of temporary by employing his own labour with watch and word etc	Per Sqm for 1 Month	
	Providing, supplying & fixing cloth ceiling inside the Hanger structure on wooden section framework. All material will be supplied by contractor & on rental basis. and after kumbhamela period removing the structure, cleaning the site & conveying the material and will be taken back by the contractor. Note: During period of kumbhamela contractor has to maintain and preserve as well as upkeep the structure of temporary by employing his own labour with watch and word etc. Completed as directed by engineer in charge.		
	Flooring:- Providing & fixing levelled flooring with 19mm block board fixed on wooden sections supports		
	Providing, supplying & fixing synthetic Needle Punch Carpet Flooring fixed/pasted on wooden floor or laid on ground. All material will be supplied by contractor & on rental basis. and after kumbhamela period removing the structure, cleaning the site & conveying the material and will be taken back by the contractor. Note: During period of kumbhamela contractor has to maintain and preserve as well as upkeep the structure of temporary by employing his own labour with watch and word etc. Completed as directed by engineer in charge.		
	All material will be supplied by contractor & on rental basis. and after kumbhamela period removing the structure, cleaning the site & conveying the material and will be taken back by the contractor. Note: During period of kumbhamela contractor has to maintain and preserve as well as upkeep the structure of temporary by employing his own labour with watch and word etc. Completed as directed by engineer in charge.		
	Electrification :- Cabling & wiring of the of the entire structure along with providing electrical fixtures such as Ceiling fans 162 nos, LED lights 162 nos plug points.(Electrical power source near the shed will be provided by NMC)		
	Providing Decorative Front Façade made with MS Steel Frame work, flex printing, Mounting &Installation		
5	Steel Table	Per No. for 1 Month	
6	PVC Chair	Per No. for 1 Month	

(Rs. In Words : _____)

Quotation Will be Opened on.19/11/2025 at 03.30 P.M (If Possible) in the Office of Executive Engineer Traffic cell, PWD Dep 1st floor, Rajiv Gandhi Bhavan, NMC Nashik

Sing & Seal of Agency

Executive Engineer

Traffic cell, PWD DEP

Nashik Municipal Corporation