

**नाशिक महानगर पालिका, नाशिक.,  
उद्याने व वृक्ष प्राधिकरण विभाग  
कोटेशन नोटीस**

जा.क्र./उद्यान/उनि-०५/४३०/२०२४, दि. २९/०२/२०२४

कामाचे नाव : - नविन नाशिक विभागातील प्र. क्र. २८ मधिल कामटवाडे शिवारातील रामेश्वर नगर उद्यानाची संरक्षक भिंत दुरूस्ती व रंगरंगोटी करणे बाबत...

कामाची मुदत :- ३० दिवस / ०१ महिना

कोटेशन फॉर्म मिळण्याची तारीख : दि. ०१/०३/२०२४ ते ०६/०३/२०२४

कोटेशन फॉर्म स्विकारण्याची तारीख : दि. ०६/०३/२०२४ दुपारी - ०३.०० पावेतो

कामाचा तपशिल :-

Sr. No.	SSR No.	Item code	Description of Item	Quantity	Rate	Unit	Amount
1	46.13	1544	Removing rich mix cement concrete etc. complete.	0.41 Cumt.	976.50	Cumt.	400.36
2	46.11	1542	Dismantling stone masonry in lime or cement mortar etc.	0.76 Cumt.	399.00	Cumt.	303.24
3	28.04	912	Providing uncoursed rubble masonry of trap /granite /quartzite / gneiss stones in cement mortar 1:6 in superstructure etc. complete.	0.67 Cumt.	6675.30	Cumt.	4,472.45
4	24.16	840	Providing and laying Cast in situ/Ready Mix cement concrete M-15 for coping to plinth or parapet, etc.	0.15 Cumt.	7327.00	Cumt.	1,099.05
5	24.08	835	Providing and laying Cast in situ/ Ready Mix cement concrete in M15 for bed blocks, foundation blocks and such other items etc.	0.27 Cumt.	7327.00	Cumt.	1,978.29
6	32.11	968	Providing sand faced plaster externally in cement mortar using approved screened sand, etc. complete.	7.19 Sqmt.	722.00	Sqmt.	5,191.18
7	32.18	974	Providing tuck pointing with cement mortar 1:3 for stone / Brick masonry etc. complete.	13.90 Sqmt.	195.70	Sqmt.	2,720.23
8	35.13	1088	Providing and applying two coats of water proof cement paint etc. complete.	162.90 Sqmt.	83.00	Sqmt.	13,520.07
9	35.09	1084	Providing and applying two coats of flat oil paint of approved colour to the old structural steel work and iron work etc. complete.	138.32 Sqmt.	89.30	Sqmt.	12,351.97
					Total Amount Rs.		42,036.84
					Add GST 18%		7,566.63
10			Royalty Charges for Natural sand to be paid to Govt.	0.46 Cumt.	237.37	Cumt.	109.19
11			Royalty Charges for All Other Minerals to be paid to Govt.	0.77 Cumt.	216.18	Cumt.	166.45
				Total of item no. 1 to 11			49,879.11

एकूण प्राकलन रक्कम रूपये - ४९,८७९/-

अक्षरी रक्कम रूपये - एकोणपन्नास हजार, आठशे एकोणऐंशी मात्र

**अटी शर्ती :**

१) सदरकामी लागणारे कोणत्याही प्रकारचे आवश्यक साहित्य मनपा पुरविणार नाही तसेच सदरकामी होणारा मजुरीचा, वाहतुकीचा व ईतर अनुशंगिक खर्च हा मक्तेदारास करावयाचा आहे. २) सदर कामाबाबतची सविस्तर माहिती व कामाचे कोटेशन फॉर्म विभागाचे उद्यान निरीक्षक/सहा. क. अभियंता यांचेकडे सार्वजनिक सुटीचे दिवस सोडून उपरोक्त नमूद मुदतीत कार्यालयीन वेळेत नविन नाशिक विभागाचे कार्यालयात उपलब्ध करून देण्यात येईल. ३) सदर काम विभागाचे उद्यान निरीक्षक/सहा. क. अभियंता सुचवितील त्याप्रमाणे विहित मुदतीत पुर्ण करून द्यावे लागेल. ४) सदर कामाचे कोटेशन दर स्विकारण्याचा अथवा नाकारण्याचा अंतिम अधिकार हा मा. उप अभियंता, उद्यान यांचा राहिल. ५) सदरकामी कोणत्याही प्रकारचे आगाऊ देयक मनपाकडून मिळणार नाही.

ज्याकोणास वरील नमूद काम वरील नमूद मुदतीत व अटिशर्तीनुसार करावयाचे असेल त्यांनी याबाबतचे आपले कोटेशन दर विहित नमुन्यात बंद पाकिटात उद्याने व वृक्ष प्राधिकरण नविन नाशिक विभागाचे कार्यालयात दि. ०६/०३/२०२४ रोजी दु. ०३.०० वाजेपावेतो आणुन द्यावेत.

Sd/-

**उप अभियंता उद्यान**  
नाशिक महानगर पालिका, नाशिक.

**NASHIK MUNICIPAL CORPORATION, NASHIK  
GARDEN & TREE AUTHORITY DEPARTMENT**

**E- Quotation (2023-24)**

**Name Of Work :-** Repairing & Colouring Rameshawar nager garden compound wall at Kamatwade shiwar  
In P. No. 28, New Nashik. Nashik - 10

**Cost put to Quotation Rs.-** 49,879/-

**Issue of Blank Quotation form -** 01/03/2024 to 06/03/2024

**Submission of sealed Quotation form -** 06/03/2024

**Time Limit -** 06 Day

Sr. No.	SSR No.	Item code	Description of Item	Quantity	Rate	Unit	Amount
1	46.13	1544	Removing rich mix cement concrete etc. complete.	0.41 Cumt.	976.50	Cumt.	400.36
2	46.11	1542	Dismantling stone masonry in lime or cement mortar etc.	0.76 Cumt.	399.00	Cumt.	303.24
3	28.04	912	Providing uncoursed rubble masonry of trap/granite/quartzite/gneiss stones in cement mortar 1:6 in superstructure including racking out joints when plastering is to be done / striking joints when no plastering is to be done on inside watering and scaffolding etc. complete.	0.67 Cumt.	6675.30	Cumt.	4,472.45
4	24.16	840	Providing and laying Cast in situ/Ready Mix cement concrete M-15 of trap/granite quartzite/ gneiss metal for coping to plinth or parapet, moulded or chamfered as per drawing or as directed including steel centering, plywood/ steel formwork compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.) With fine aggregate (Crushed sand VSI Grade)	0.15 Cumt.	7327.00	Cumt.	1,099.05
5	24.08	835	Providing and laying Cast in situ/ Ready Mix cement concrete in M15 of trap / granite/quartzite/ gneiss metal for bed blocks, foundation blocks and such other items including bailing out provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finishis to be honeycombed surface only.	0.27 Cumt.	7327.00	Cumt.	1,978.29

			Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.),				
6	32.11	968	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using water proofing compound at 1 Kilogram per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc. complete.	7.19 Sqmt.	722.00	Sqmt.	5,191.18
7	32.18	974	Providing tuck pointing with cement mortar 1:3 for stone / Brick masonry including scaffolding and curing etc. complete.	13.90 Sqmt.	195.70	Sqmt.	2,720.23
8	35.13	1088	Providing and applying two coats of water proof cement paint of approved manufacture and of approved colour to the plastered surfaces etc. complete.	162.90 Sqmt.	83.00	Sqmt.	13,520.07
9	35.09	1084	Providing and applying two coats of flat oil paint of approved colour to the old structural steel work and iron work previously painted in building including scaffolding, if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete.	138.32 Sqmt.	89.30	Sqmt.	12,351.97
					<b>Total Amount Rs.</b>		<b>42,036.84</b>
					<b>Add GST 18%</b>		<b>7,566.63</b>
10			Royalty Charges for Natural sand to be paid to Govt.	0.46 Cumt.	237.37	Cumt.	109.19
11			Royalty Charges for All Other Minerals to be paid to Govt.	0.77 Cumt.	216.18	Cumt.	166.45
					<b>Total of item no. 1 to 11</b>		<b>49,879.11</b>

Say Rs. :- 49,879.00

Say Rs.(Inwards):- Forty Nine Thousand, Eight Hundred Seventy Nine Only.

I / We have gone through the all details of the work as mentioned above. As well as, have gone through the details of all the Terms and conditions set for this work. I / We Are hereby agreed to execute the above work accepting all these Terms & Conditions

Words-----Percentage) Above / Below estimated rates.

Sd/-

Contractor Signature

**Deputy Engineer**  
**Garden Department**  
Nashik Municipal Corporation, Nashik