

## नाशिक महानगरपालिका, नाशिक

मलनि:सारण यांत्रिकी विभाग

ई-कोटेशन नोटीस क्रमांक २०२१-२२

**कामाचे नाव :-** मनपाचे पंचक मलनि:सारण केंद्राची लॅबरूमची दुरुस्ती व त्या अनुषंगिक कामे

करणे बाबत.

१. कामाची मुदत :- ३ महिने

२. कोटेशन फॉर्म मिळण्याचे ठिकाण :- कार्यकारी अभियंता(यां) ,

राजीव गांधी भवन, म.न.पा. नाशिक

३. काम करणेचे ठिकाण :- विषयांकित

४. कोटेशन फॉर्म मिळण्याची तारीख :- दिनांक ० ३/१२/२०२१ ते ०९/१२/२०२१

५. कोटेशन जमा करण्याची अंतिम तारीख :- ०९/१२/२०२१ दुपारी १.०० वाजेपर्यंत

६. कोटेशन जमा करण्याचे ठिकाण :- कार्यकारी अभियंता(यां) ,

राजीव गांधी भवन, म.न.पा. नाशिक

Sd/-

कार्यकारी अभियंता(यां) ,  
नाशिक महानगरपालिका, नाशिक

# NASHIK MUNICIPAL CORPORATION SEWAGE MECHANICAL DEPARTMENT

E Quotation No:- /2021-22

**Name Of Work :-** Repaing LAB and allied work at panchak STP of NMC.

**Estimated Cost:-** Rs.2,94,739/-

Sr No	Description	QTY	Unit	Rate	Total
1	Providing and constructing granite kitchen platform with fixing of stainless steelsink 600mmx450mm size as per detailed drawing including vertical both side polished kadappa stone 25 to 30mm thick supports with kadappa top 35 to 40mm thick and polished granite 16 to 20mm top with side strips of granite at front and both sides of platform raised with two vertical granite supports 15cm height and top granite of 75x40cm including cutting, opening for sink of required size in kadappa as well as granite etc. complete. (Platform top size 5.00 m x 0.60 m and height is 0.75 m)	14.09	Sq M	9180	129342.53
2	Providing and fixing stainless steel sink of size 600x510x200 mm including coupling, outlet pipe, elbow and other necessary fitting, finishing etc. complete.	1	No	14515	14515.00
3	Providing and fixing black kadappa stone shelves 25mm thick machine polished, extending the polish up to 20cm width on lower side, rounding corners, laying in position jointing with bedding cement mortar 1:4 proportion curing etc etc. complete	5.355	Sq M	1114	5965.47
4	Providing and laying ceramic tiles having size 30cm.x45cm. confirming to corresponding I.S.b for dado and skirting in required position with ready made adhesive mortar of approved quality on plaster of 1:2 cement mortar including joint filling with white /colour cements lorry cleaning curing etc. complete	10.3	Sq M	1171	12056.62
5	Providing and fixing H.D.P container Syntex or alike one piece moulded water tank made out of high density polythylene and built corrugated inclusive of delivery up to destination hoisting and fixing of accessories such as inlet, outlet overflow pipe inclusive of all tanks capacity between 200 to 1000 liters	500	Liters	13	6500.00
6	Providing and fixing H.D.P container Syntex or alike one piece moulded water tank made out of low density polythylene and built corrugation inclusive of delivery up to destination hoisting and fixing of accessories such as inlet, outlet over flow of all tanks capacity above 1000 to 20,000 litres	2000	Liters	11	22000.00

7	Providing and applying white-wash in two coats on old/new plastered or masonry surfaces and asbes to scement sheets including scaffolding and preparing the surface by brushing and brooming down etc. complete	210.8	Sq M	10	2108.4 4
8	Providing and applying washable oil-bound distemper of approved colour and shade to old and new surfaces in two coats including scaffolding ,preparing the surfaces.(excludingtheprimer coat.) etc. complete.	210.8	Sq M	43	9066.2 8
9	Providing and fixing inposition.( asperI.S.1868/1982) Aluminium sliding window of two tracks with rectangular pipe having over all dimension 63.50x38.10x1.02 mm at weight 0.547 Kilogram/ Running metre. and window frame bottom track section 61.85x31.75x1.20 mm at weight 0.695 Kilogram/Runningmetre. Top and side track section 61.85x31.75x1.30 mm at weight 0.659 Kilogram/Running metre. The shutters should be of bearing bottom 40x18x1.25 mm at weight 0.417 Kilogram/Running metre. Interlocking section 40x18x1.10 mm at weight 0.469Kilogram/ Runningmetre. And handle section 40x18x1.25 mm at weight 0.417Kilogram/ Running metre. and top section 40x18x1.25mm at weight 0.417Kilogram/ Running metre. As per detailed drawings and as directed by Engineer incharge with all necessary Aluminium sections fixtures and fastening ssuch as roller bearing innyloncasting and selflocking catch fitted in vertical section of shutter including 5 mm thick plain glass with all required screw sand nuts etc, complete. With colour Anodising without box	2.75	Sq M	5272	14498. 00
10	Solid Core Flush door Single leaf Providing and fixing factory made solidcore flush door insingle leaf 35 mm thick, decorative types, of exterior grade, as per detailed drawings, conforming to I.S.:2202-1962 (Revised) with approved face veneerson both faces with/without glazing and venetiansin the positions show nonthe drawing sor as directed, all necessary beads, moulding and lipping, hold fasts, mat finish stainless steel fixtures fastenings, finishing with french-polish /waxing complete. (withoutdoorframe). (Sample to be got approved from Ex.Engineer before use)Commercial Hard Wood shutter(PWD SSR 2020-21 item no.1871 pg.313)	1.832	Sq M	2750	5037.4 5
11	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:3 without neeru finish to concrete or brick surfaces,in all position including scaffolding and curing etc. complete	30.02	Sq M	274	8226.5 8
12	Providing fine cement finish 1.5mm thick over green plaster surface including scaffolding curing etc. complete.	30.02	Sq M	66	1981.5 8

13	Providing and fixing M.S. gate 2.5 M wide for compound with 40 mm dia G.I. pipe, approved grill work, RCC M-150 side pillars of 25 cm x 40 cm x 2.5 M height, its foundation, finishing, painting, etc. Complete	1	No	31862	31862.00
					26315.95
Total					31579.19
Add GST 12%					29473.9
<b>TOTAL</b>					<b>29473.9</b>

I/We here by agreed to execute the above work at the Rs.

(            % above/below the estimated rate) Only

**Contractor**

**Executive Engineer(M)**  
Nashik Municipal Corporation